
### Closure Report for the 43 Area Morale, Welfare, and Recreation (MWR) Gas Station Site 43286

(Includes: Documentation of Verification Soil Sampling)
Marine Corps Base Camp Pendleton



Prepared for



NAVAL FACILITIES ENGINEERING SERVICE CENTER 1100 23<sup>rd</sup> Avenue Port Hueneme, California 93043

NAVFAC SOUTHWEST 1220 Pacific Highway San Diego, California 92132-5190

CONTRACT NUMBER: N47408-01-D-8207 TASK ORDER: 0115 by

## **Battelle**

**Environmental Restoration Department** 

505 King Avenue Columbus, Ohio 43201-2693

**April 2006** 

## Closure Report for the 43 Area Morale, Welfare, and Recreation (MWR) Gas Station Site 43286 (Includes: Documentation of Verification Soil Sampling) Marine Corps Base Camp Pendleton

Contract No.: N47408-01-D-8207 Task Order: 0115

#### **Prepared for:**

Naval Facilities Engineering Service Center 1100 23rd Avenue Port Hueneme, California 93043-4301

and

Naval Facilities Engineering Command Southwest 1220 Pacific Highway San Diego, California 92132-5190

Prepared by:

BATTELLE 505 King Avenue Columbus, Ohio 43201

## Closure Report for the 43 Area Morale, Welfare, and Recreation (MWR) Gas Station Site 43286 (Includes: Documentation of Verification Soil Sampling) **Marine Corps Base Camp Pendleton**

25APRILOG

Date

Approved:

Robert Janosy, P.G.

Battelle Memorial Institute

Project Manager/Geologist

ii

#### **CONTENTS**

Section 1	.0: INTRODUCTION	1
1	.1 Objectives	1
1	.2 Site Background and Location	1
	.0: SITE ENVIRONMENTAL ACTIVITIES	
	.1 UST Removal	
	.2 Site Assessment and Well Installation	
	.3 IAS/SVE Remediation System	
	.4 Groundwater Monitoring/Verification Groundwater Sampling	
	.5 Surface Water Study	
2	.o vernication son sampling	J
Section 3	.0: CLEANUP OBJECTIVES	
_	.1 Soil Cleanup Goals	
3	.2 Groundwater Cleanup Goals	7
Section 4	.0: ASSESSMENT OF IMPACTS	
4	.1 Nature and Extent of Contamination	
	4.1.1 Soil	
	4.1.2 Groundwater	
	4.1.3 Surface Water	
1	2 Site Geology	
	.3 Site Hydrogeology	
	.4 Evaluation of Potential Impact to Water Resources	
	•	
Section 5	.0: SUMMARY	12
Section 6	.0: REFERENCES	13
	A: DOCUMENTATION OF IAS/SVE SYSTEM REMOVAL B: DOCUMENTATION OF VERIFICATION SOIL SAMPLING	
	FIGURES	
Figure 1.	Site Assessment and Mitigation Process Flowchart	
Figure 2.	Site 43286 Vicinity Map	
Figure 3.	Site 43286 Location Map	
Figure 4. Figure 5.	Site 43286 Site Map	
Figure 5. Figure 6.	Site 43286 Quarterly Groundwater Sample Results Site 43286 Verification Soil Sample Results	
115010 0.	Site 13266 verification bon bumple results	
	TABLES	
Table 1.	Summary of Site 43286 Environmental Activities	
Table 2.	Site 43286 Soil and Groundwater Cleanup Goals	

#### ABBREVIATIONS AND ACRONYMS

AC/S ES Assistant Chief of Staff, Environmental Security

amsl above mean sea level

BTEX benzene, toluene, ethylbenzene, and total xylenes

btoc below top of casing

CAP Corrective Action Plan
CME Central Mine Equipment
COC contaminant of concern

CSWRCB California State Water Resources Control Board

DEH (San Diego County) Department of Environmental Health

DVE dual vacuum extraction

EHS Environmental Health Services

GAC granular activated carbon

HSA hollow-stem auger

IAS in situ air sparging ID identification

LNAPL light nonaqueous-phase liquid LOP local oversight program

LUFT Leaking Underground Fuel Tank

MCB Marine Corps Base

MCL maximum contaminant level MTBE methyl-*tert*-butyl ether

MWR morale, welfare, and recreation

NAVFAC Naval Facilities Engineering Command

ND non-detect

NFESC Naval Facilities Engineering Service Center

NIRIS Navy Installation Restoration Information Solution

OHM Remediation Services, Inc.

PRG preliminary remediation goal

RAP Remedial Action Plan RPM Remedial Project Manager

RWQCB Regional Water Quality Control Board, San Diego Region

SAM site assessment and mitigation

SPLP synthetic precipitation leaching procedure

SVE soil vapor extraction

TMB trimethylbenzene

TPH-D total petroleum hydrocarbons extractable as diesel total petroleum hydrocarbons purgeable as gasoline TPH-MO total petroleum hydrocarbons extractable as motor oil

UST underground storage tank

VAP voluntary assistance program

#### **Section 1.0: INTRODUCTION**

This Closure Report was prepared for the Department of Navy, Naval Facilities Engineering Command (NAVFAC) Southwest under Task Order No. 0115 of the United States Naval Facilities Engineering Service Center (NFESC) Contract No. N47408-01-D-8207. The Closure Report addresses the 43 Area Morale, Welfare, and Recreation Gas Station (Site 43286), located at Marine Corps Base (MCB) Camp Pendleton.

#### 1.1 Objectives

The objectives of the Closure Report are as follows:

- Document verification soil sampling activities and results.
- Summarize previous environmental activities conducted at Site 43286.
- Meet the requirements of the Regional Water Quality Control Board, San Diego Region (RWQCB) and the San Diego County Department of Environmental Health (DEH) for the submittal of a Closure Report.
- Provide a recommendation of no further action for the site.

Site 43286 is regulated under the California State Water Resources Control Board's Leaking Underground Fuel Tank (LUFT) program (CSWRCB, 1989) as administered by the RWQCB. The document guiding the assessment, remediation, and closure process at the site is the *Site Assessment and Mitigation (SAM) Manual* (DEH, 2004). Figure 1 is a flowchart that summarizes the site assessment and mitigation process in San Diego County. Currently, Site 43286 is in the post-remedial monitoring process.

The following subsections of Section 1.0 describe the site background and location. Section 2.0 presents a summary of the environmental activities performed at Site 43286, which includes underground storage tank (UST) removal, site assessment and well installation, operation of the in situ air sparging/soil vapor extraction (IAS/SVE) remediation system, groundwater monitoring, surface water study, and verification soil sampling. Section 3.0 summarizes the cleanup objectives for the Site 43286, and Section 4.0 is an assessment of impacts at the site. Section 5.0 summarizes the report and makes a recommendation, and Section 6.0 lists references cited in the report. Appendix A contains documentation of IAS/SVE system removal, and Appendix B contains documentation of the verification soil sampling.

#### 1.2 Site Background and Location

The following list summarizes the site identification data:

Site Address: Buildings 43286 and 43287, 43 Area

Camp Pendleton, CA 92055

Facility Name: Morale, Welfare, and Recreation (MWR)

Gas Station

**Environmental Health Services** 

(EHS) Case No: H05939-095
Assessor's Parcel No.: 101-000-00
RWQCB Case No: SMC: 50-2962.05

Property Owner:

Tank Owner:

United States Marine Corps
United States Marine Corps
United States Marine Corps
United States Marine Corps

MCB Contact: Mr. Chet Storrs

Assistant Chief of Staff

Environmental Security (AC/S ES)

Building 22165

Camp Pendleton, CA 92055-5008

(760) 725-9774

Remedial Project Manager (RPM): Herb Doughty

NAVFAC Southwest, Code OPCE.HD

1220 Pacific Highway San Diego, CA 92132-519

(619) 532-4714

Responsible Party: United States Marine Corps

MCB Camp Pendleton is located in northern San Diego County, CA, and covers approximately 125,000 acres of land bordered on the west by the Pacific Ocean. Site 43286 is an active gasoline station located in the center portion of MCB Camp Pendleton on Las Pulgas Road. The site is located within the Las Flores Groundwater Basin; however, the nearest downgradient drinking water well is more than 4 miles from the site. The site is bounded by undeveloped land to the north and south, Las Flores Creek to the east, and Las Pulgas Road to the west. Figure 2 is an area map showing the location of MCB Camp Pendleton and Site 43286. Figure 3 is a location map of the 43 Area identifying Site 43286, and Figure 4 is a site map of Site 43286.

#### **Section 2.0: SITE ENVIRONMENTAL ACTIVITIES**

This section summarizes the environmental activities conducted at the Site 43286 from 1993 to present. A detailed chronology of site environmental activities is presented in Table 1.

#### 2.1 UST Removal

In October 1993, two 10,000-gallon gasoline USTs and one 550-gallon waste oil tank were removed from the site. The release history and the total volume of fuel hydrocarbons released to the subsurface are unknown.

#### 2.2 Site Assessment and Well Installation

In 1994, nine borings (B1-B9) and three groundwater monitoring wells (43286-MW01, 43286-MW02, and 43286-MW03) were installed and sampled as part of the initial site assessment (IT Corp., 1994). This assessment indicated that soil and groundwater at the site had been impacted by a release of fuel hydrocarbons. Analytical results showed that total petroleum hydrocarbons quantified as gasoline (TPH-G) and benzene were present in Site 43286 soil at concentrations of 5,300 mg/kg and 2 mg/kg, respectively. In addition, groundwater was found to be impacted with TPH-G, benzene, toluene, ethylbenzene and xylenes at 48,000  $\mu$ g/L, 3,060  $\mu$ g/L, 11,400  $\mu$ g/L, 1,080  $\mu$ g/L, and 6,550  $\mu$ g/L, respectively. In August and September 1995, an additional boring (B10) was advanced, and an additional groundwater monitoring well (43286-MW04) was installed (OHM, 1995). Aquifer pump testing, soil vapor extraction (SVE), and dual vacuum extraction (DVE) pilot-scale testing was performed in September and October of the same year (OHM, 1996).

During March and April 1997, nine additional borings (HP-1 through HP-9) and four groundwater monitoring wells (43286-MW01A, 43286-MW05A, 43286-MW05B, and 43286-MW06) were installed and sampled at Site 43286. In addition, hand-augered borings were taken in the Las Flores Creek embankment, and temporary stream channel piezometers were installed in the Las Flores Creek (OHM/M&E, 1997).

#### 2.3 IAS/SVE Remediation System

In 1998, Battelle installed a remediation system consisting of in situ air sparging with soil vapor extraction (Battelle, 1998a) and field design testing activities were conducted from December 11, 1998 through January 19, 1999. Full-scale operation of the system began on February 19, 1999, and continued until August 4, 2000. Monitoring wells 43286-MW07A and 43286-MW07B were installed as part of this effort.

During operation of the IAS/SVE system, contaminant removal was significant. Approximately 572 lb of petroleum hydrocarbons were removed by the SVE system and treated on-site by either a thermal oxidizer or granular activated carbon (GAC) system. Samples collected from the monitoring wells located in the most impacted areas (i.e., 43286-MW01A, 43286-MW04, and 43286-MW07B) showed between 95.8 and 99.8% removal of all contaminants of concern (COCs) (Battelle, 2001).

From August 2000 until August 2001, the IAS/SVE system was not in operation and post-operation quarterly groundwater monitoring was initiated to determine whether contaminant rebound would occur. In 2002, Battelle removed the IAS/SVE system and abandoned the IAS/SVE system wells after receiving approval from the RWQCB, as contaminant concentrations from all site wells during the

four quarterly groundwater monitoring events were stable or decreased (Battelle, 2002; RWQCB 2002). Copies of the IAS/SVE well, soil-gas monitoring point, and piezometer destruction diagrams documenting the system removal are provided in Appendix A.

#### 2.4 Groundwater Monitoring/Verification Groundwater Sampling

From September 1995 to July 2005, twenty-nine (29) groundwater monitoring events were conducted and reported for Site 43286 (OHM, 1997; Battelle, 1998b, Battelle, 1999, 2000a, 2001a, 2001b, 2001c, 2002, 2003a, 2004, 2005). All ten site wells were installed by late 1998 and monitored by Battelle. Nine piezometers located in the Las Flores streambed were added to the quarterly groundwater monitoring network and sampled from May 1999 to November 2000. All groundwater monitoring events conducted after the IAS/SVE system was shut down is considered verification groundwater sampling.

Seven quarters of groundwater monitoring were conducted by OHM from September 1995 to July 1997 (OHM, 1997). Battelle resumed groundwater monitoring activities at Site 43286 and performed quarterly events from February 1998 to August 2000 (Battelle, 1999, 2000a, 2001a). After the IAS/SVE system was shutdown on August 4, 2000, Battelle conducted verification groundwater sampling for one year (November 2000, February 2001, April 2001, and July 2001) to evaluate the potential for contaminant rebound (Battelle, 2001a, 2001b, 2001c). In 2002, after groundwater monitoring suggested that no significant rebound was occurring (Battelle, 2001c), the RWQCB requested that groundwater monitoring be conducted semiannually for two years (RWQCB, 2002).

Battelle resumed verification groundwater sampling and conducted semi-annual monitoring for two years (July 2002, January 2003, July 2003, and January 2004) as recommended by the RWQCB (Battelle 2002, 2003a, 2004). In January 2005, the RWQCB requested that a minimum of two additional groundwater monitoring events be conducted during the 1<sup>st</sup> and 2<sup>nd</sup> quarters 2005 with the intention of capturing possible high groundwater levels that might be present at the site (from historically dry wells) due to the significant winter 2004 rainfall (RWQCB, 2005a). Although the RWQCB recommended sampling during the 1<sup>st</sup> and 2<sup>nd</sup> quarters 2005, actual field activities could not commence until the 2<sup>nd</sup> quarter 2005 (Battelle, 2005). Figure 5 presents the groundwater results for the last four monitoring events conducted at the site.

#### 2.5 Surface Water Study

Las Flores Creek is located adjacent to Site 43286 with the main channel of the creek located approximately 200 ft east of the site. In order to evaluate the impact of the gasoline release from Site 43286, surface water and groundwater sampling was performed at Las Flores Creek in 1999 (Battelle, 2000b). Results from the study indicated the presence of an upward vertical hydraulic gradient, which suggested the creek was gaining (i.e., groundwater contributes to the stream flow).

The groundwater beneath the creek was sampled from nine piezometers which were installed to the east/southeast of Site 43286 within the bed of the Las Flores Creek. The piezometers were sampled three times from May 1999 through November 1999 (Battelle, 2000b). Initially, methyl-*tert*-butyl ether (MTBE) and xylenes were detected in piezometers at maximum concentrations of 88  $\mu$ g/L and 0.5  $\mu$ g/L, respectively. The final piezometer sampling event occurred in November 2000, roughly one year after the IAS/SVE system had been initiated. During this event, MTBE and xylenes were detected at maximum concentrations of 6.3  $\mu$ g/L and 1.1  $\mu$ g/L, respectively. The decreased concentrations of MTBE located downgradient of Site 43286 was attributed to the effectiveness of the IAS/SVE system. The IAS/SVE system drastically reduced the concentrations of COCs in groundwater within the system's radius of influence, effectively removing the source of contamination in groundwater.

Surface water was sampled three times from August 1999 to February 2000 in the Las Flores Creek and results indicated that surface water had been impacted by benzene, toluene, ethylbenzene, and total xylenes (BTEX) constituents at low concentrations, which were below cleanup goals for groundwater (Battelle, 2000b). The first sampling events took place in August 1999, roughly six months after the initiation of the IAS/SVE system. Very low levels of BTEX constituents (benzene, toluene, and xylenes at 0.61, 0.5, and 0.5  $\mu$ g/L, respectively) were detected in the first sampling event. The two subsequent events occurred in November 1999 and February 2000, roughly nine months and one year after initiating the system; no COCs were detected in either of these sampling events.

Findings of the study concluded that Site 43286 currently poses minimal threats to surface water and groundwater downgradient of the site. Concentrations of groundwater in the source area have been reduced to levels below the groundwater cleanup goals. Furthermore, sampling performed concurrently with the IAS/SVE system indicated that COCs downgradient of Site 43286 have decreased to concentrations below cleanup goals in the creek bed piezometers, and to non-detectable levels in the Las Flores Creek surface water.

Four additional quarters of surface water and groundwater sampling at Las Flores Creek were continued from February 2000 to November 2000 as part of the verification/groundwater monitoring effort (Battelle, 2001a).

#### 2.6 Verification Soil Sampling

As part of the post-corrective action process, verification soil sampling was conducted at Site 43286. The *Work Plan for Soil Verification Sampling at Site 43286, Marine Corps Base Camp Pendleton* was submitted after groundwater monitoring (verification groundwater sampling) suggested that contaminant rebound was not occurring following shutdown of the IAS/SVE system (Battelle, 2003b). Currently, ten post-IAS/SVE groundwater monitoring events, which constitute the verification groundwater sampling, have been conducted with no reported contaminant rebound.

Verification soil sampling was conducted on December 2, 2005 as outlined in the work plan (Battelle, 2003b). Soil sampling was performed at locations within identified contaminated areas and the IAS/SVE radius of influence. Sampling locations were surveyed on-site with a hand-held GPS unit. No boring permit with DEH was necessary because all boreholes were advanced less than 20 ft and no groundwater was encountered. Documentation of the verification soil sampling effort is presented in Appendix B, including copies of the analytical report, associated data validation packets, and survey plot.

In all, four soil samples (43286-SV1 through 43286-SV4) were collected from 13 to 16.5 ft bgs using a Central Mine Equipment (CME)-75 hollow-stem auger (HSA) and analyzed for TPH-G, BTEX, and MTBE. Figure 6 presents the locations of the verification soil samples as well as the analytical results. In two of the four verification soil samples (43286-SV2 and 43286-SV3), TPH-G, BTEX, and MTBE were not detected at levels above reporting limits. Minor detections of TPH-G, ethylbenzene, and xylenes were reported at 7 mg/kg, 18  $\mu$ g/kg, and 15  $\mu$ g/kg, respectively, from 43286-SV1. TPH-G was detected in 43286-SV4 at 39 mg/kg. Synthetic Precipitation Leaching Procedure (SPLP) testing was performed on 43286-SV1 for BTEX and MTBE, and none of the compounds analyzed for were measured at detectable levels. All boreholes were properly grouted with Portland cement.

In accordance with Assembly Bill 2886 (Water Code Sections 13195-13198), Battelle has completed an electronic data format upload for Site 43286 via the Internet to CSWRCB's GeoTracker System. For this closure report, soil laboratory data from the soil verification samples, location data (i.e.,

location of soil borings), and a site map were submitted. Electronic data uploads included the following major activities:

- 1. Obtaining a unique Global Identification (ID) for each site.
- 2. Uploading a list of "Field\_Point\_Names" to GeoTracker.
- 3. Providing the Global ID and Field Point Names to the analytical laboratory on the chain of custody.
- 4. Ensuring that the field point names, Global ID, and all laboratory data were correct within each electronic submission file.
- 5. Submitting electronic compliance data via the GeoTracker Internet site.

The data submittal for the December 2005 verification soil sampling as well as an electronic copy of this report have been uploaded to the GeoTracker Web site. In addition, the soil data will be entered into the Navy Installation Restoration Information Solution (NIRIS) database as described in current Environmental Work Instruction #6 (Environmental Data Management and Required Electronic Delivery Standards). Data will be compiled with spatial and temporal qualifiers so that it will be possible to rapidly plot the concentration of target analytes at each sampling point.

#### **Section 3.0: CLEANUP OBJECTIVES**

Soil and groundwater cleanup goals were established as part of the Corrective Action Plan (CAP) (OHM, 1998). Corrective action activities at Site 43286 were conducted to address the groundwater contamination resulting from gasoline releases. A combination of both UST removal and the operation of an IAS/SVE system were implemented with the intent to remove and/or destroy virtually mobile contamination (and sources of contamination) in the subsurface to meet soil and groundwater cleanup goals.

A dual cleanup standard for soil has been accepted, and remediation will be considered successful if confirmation soil samples from previously contaminated zones contain non-detectable concentrations of leachable BTEX and MTBE (using SPLP test), or if their total concentrations are less than the values listed in Table 2. These thresholds define concentrations in soil that pose minimal risk to underlying groundwater resources, and are reflective of current drinking water maximum contaminant levels (MCLs) (California Code of Regulations, 2003).

The IAS/SVE system implemented at this site was intended to address the area of shallow, unsaturated soils and groundwater that exceed the cleanup criteria. It has been established that groundwater levels are below cleanup goals and that rebound is not occurring.

#### 3.1 Soil Cleanup Goals

The Final Remediation Work Plan for the 43 Area Morale, Welfare, and Recreation (MWR) Gas Station, Marine Corps Base Camp Pendleton outlined that soil remediation be considered successful if soil verification samples from previously contaminated zones contain leachable concentrations (using the SPLP test) of BTEX and MTBE below groundwater MCLs (Battelle, 1998a) (Table 2). Analytical results (including SPLP) from the soil verification samples indicate that soil cleanup goals have been met at Site 43286.

#### **3.2** Groundwater Cleanup Goals

As stated in the revised final remediation work plan (Battelle, 1998a), groundwater cleanup areas are defined by the presence of BTEX and MTBE concentrations that exceed groundwater cleanup goals as observed during the site assessment activities. Site-wide groundwater monitoring has been conducted at Site 43286 since September 1995, and sufficient data show that the IAS/SVE system has been effective at reducing contaminant concentrations in groundwater. The system was shut down in August 2000 and put on standby status while groundwater monitoring (verification groundwater sampling) continued for contaminant rebound.

As reported from the last groundwater sampling event (July 2005), detectable concentrations of BTEX, MTBE, TPH-G, total petroleum hydrocarbons quantified as diesel (TPH-D), 1,2,4-trimethylbenzene (1,2,4-TMB), and 1,3,5-TMB have consistently decreased in historically contaminated wells and are currently below cleanup goals (Table 2).

#### **Section 4.0: ASSESSMENT OF IMPACTS**

This section describes the current nature and extent of contamination at Site 43286, the regional and site geology and hydrogeology, and a screening to determine whether the site has the potential to meet the criteria required for a low-risk fuel-contaminated site (RWQCB, 1996). An assessment of the impacts at Site 43286 is presented by using the guidelines outlined in the *California Underground Storage Tank Regulations* (California Code of Regulations, 2000).

#### 4.1 Nature and Extent of Contamination

The current nature and extent of contamination in soil, groundwater, and surface water are discussed in the following subsections.

- **4.1.1 Soil.** Verification soil samples collected at Site 43286 indicated that only minor residual soil contamination exists at the site. Detectable concentrations of targeted compounds were present only in 43286-SV1 and 43286-SV4. In 43286-SV1, TPH-G, ethylbenzene, and xylenes were detected at 7 mg/kg, 18 μg/kg, and 15 μg/kg, respectively; and in 43286-SV4, TPH-G was detected at 39 mg/kg. The detected concentrations of ethylbenzene and xylenes were below the established soil cleanup goals of 68 mg/kg and 175 mg/kg. No cleanup goals have been established for TPH-G.
- **4.1.2 Groundwater.** Verification groundwater samples collected at Site 43286 following shutdown of the IAS/SVE system indicated that only residual groundwater contamination exits at the site. Targeted compounds such as BTEX and MTBE are at levels below cleanup goals. During the 2005 sampling events, MTBE was detected in wells 43286-MW03, 43286-MW05A, and 43286-MW07B at maximum concentrations of 0.71 μg/L, 3.0 μg/L, and 4.5 μg/L, respectively, which are all below the final groundwater cleanup goal of 13 μg/L. Also in 2005, TPH-D was detected in well 43286-MW04 in both the primary and duplicate sample at concentrations of 0.10 mg/L and 0.068 mg/L, respectively, which are at and below the taste and odor threshold value of 0.10 mg/L. This was the first detection of TPH-D in 43286-MW04 since April 2001. TPH-D, TPH-G, ethylbenzene, xylene, MTBE, 1,3,5-TMB, and 1,2,4-TMB were detected in 43286-MW05A at concentrations of 0.13 mg/L, 0.088 mg/L, 0.50 μg/L, 1.2 μg/L, 3.0 μg/L, 2.4 μg/L, and 4.7 μg/L, respectively. The April 2005 sampling event represents the only sampling of 43286-MW05A since February 1998 and was possible only due to groundwater being present in the historically dry well. In 2005, no chemical was detected in groundwater at concentrations greater than the cleanup levels established for Site 43286.
- **4.1.3 Surface Water.** Initial surface water and groundwater analytical results from the 1999-2000 surface water study of the adjacent Las Flores Creek indicated that the creek was impacted with targeted contaminants originating from Site 43286. However, because the study was conducted concurrently with the operation of the IAS/SVE system, concentrations of those target contaminants (BTEX and MTBE) in groundwater beneath the creek and surface water samples were gradually reduced either to non-detectable levels or below groundwater cleanup goals. Findings of the study concluded that Site 43286 currently poses minimal threats to surface water and groundwater downgradient of the site.
- **4.1.4 Nonaqueous-Phase Liquids.** Light, nonaqueous-phase liquid (LNAPL) has not been observed since the IAS/SVE system was shut down in August 2000. Due to the lack of free product, LNAPL is no longer a concern.

#### 4.2 Site Geology

Geologic materials underlying Site 43286 are comprised of unconsolidated fill (sand, clayey silt) and alluvium (interbedded sands, silts, and clays). Fill material generally comprises the uppermost 5 to 15 ft of the subsurface. Asphalt and concrete cover much of the site's surface and are likely to preclude significant vertical recharge from infiltration.

#### 4.3 Site Hydrogeology

Two distinct hydrostratigraphic units appear to exist underneath the site. The upper unit, apparently unconfined, spans the base of the fill to a clay bed, approximately 4 ft thick, which may act as a confining unit on the underlying deeper zone. Differences in water levels between the two zones measured in three well pairs (43286-MW01 and 43286-MW01A, 43286-MW05 and 43286-MW05A, and 43286-MW07 and 43286-MW07A) suggest that the hydraulic head in the lower zone may be 1 to 3 ft higher than in the upper zone. The average depth to groundwater at the site is approximately 15 ft, with observed seasonal fluctuations in groundwater elevation of 2 ft. The groundwater flow direction is towards the southeast.

Site 43286 is located in the Las Flores groundwater basin, with surface drainage directed towards the east. The site lies approximately 200 ft north of Las Flores Creek. A 1999-2000 surface water study determined that site groundwater discharges into the creek (a gaining stream) (Battelle, 2000b).

#### **4.4** Evaluation of Potential Impact to Water Resources

This section discusses the proximity and quality of nearby surface water and groundwater, and the current/potential beneficial uses of this water. Las Flores Creek is the nearest surface water body and is located adjacent to Site 43286 with the main channel of the creek located approximately 200 ft east of the site. Based on the results of the 1999-2000 surface water study, there is minimal to no threat of Las Flores Creek becoming impacted with target contaminants at levels above cleanup goals because Site 43286 groundwater has been remediated to these concentrations. Similarly, the three production wells (10S/5W18E2, 10S/5W18M3, and 10S/5W18M4) located in the Las Flores watershed, are clustered approximately 4.25 miles to the south of the site and are not likely to be impacted.

The RWQCB has issued supplemental guidance which aids in determining whether a UST site in California qualifies as a "low-risk soils-only" case or a "low-risk groundwater" case. Based on this guidance, because both residual soil and groundwater impacts exist at Site 43286, the site does not qualify as a low-risk soils-only site as defined in the *Interim Guidance on Required Cleanup at Low-Risk Fuel Contaminated Sites* (RWQCB, 1996). However, because the contaminated plume is stable and not migrating, the site was screened to determine if it has the potential to meet the criteria required for low-risk groundwater sites. These criteria are presented below, along with an explanation of how the site currently meets, or does not meet, the criteria.

- 1. Groundwater has been impacted, the leak has been stopped, and ongoing sources, including free product, have been removed or remediated to the extent possible.
  - Two 10,000-gallon gasoline USTs and one 550-gallon waste oil UST were removed from the site in October 1993.
  - Groundwater at the Site 43286 currently is impacted with targeted contaminants, but at levels below cleanup values. In 2005, benzene and toluene were not detected

above reporting limits, and maximum detected concentrations of ethylbenzene, xylenes, and MTBE were 0.50  $\mu g/L$ , 1.2  $\mu g/L$ , and 4.5  $\mu g/L$ , respectively, compared to their corresponding cleanup goals of 680  $\mu g/L$ , 1,750  $\mu g/L$ , and 13  $\mu g/L$ . TPH-D and TPH-G were detected at 0.13 mg/L and 0.088 mg/L, respectively, compared to taste and odor threshold values of 0.10 mg/L and 0.005 mg/L.

- An IAS/SVE system was installed and operated by Battelle at Site 43286 from February 1999 through August 2000. The system was effective at removing 572 lb of petroleum hydrocarbons, which represents a 95.8 to 99.8% reduction in groundwater contamination.
- 2. The site has been adequately characterized.
  - In 1994, nine borings (B1-B9) and three groundwater monitoring wells (43286-MW01, 43286-MW02, and 43286-MW03) were installed and sampled. Investigation indicated that soil and groundwater at the site had been impacted by a release of fuel hydrocarbons.
  - In August and September 1995, OHM installed and sampled one boring (B10) and one groundwater monitoring well (43286-MW04).
  - During March and April 1997, OHM/M&E installed and sampled nine borings (HP-1 through HP-9) and four groundwater monitoring wells (43286-MW01A, 43286-MW05A, 43286-MW05B, and 43286-MW06), hand-augered borings into the Las Flores Creek embankment, and installed temporary stream channel piezometers.
  - From September 1995 to July 1997, OHM conducted 7 quarterly groundwater monitoring events. From February 1998 to July 2001 Battelle conducted 16 quarterly groundwater monitoring events, and then conducted semi-annual groundwater monitoring for two years from July 2002 to January 2004. Finally, two concurrent quarterly monitoring events were performed in April and July 2005.
  - From 1999 to 2000, surface water and groundwater analyses were performed at Las Flores Creek in order to evaluate the impact of site contaminants to this ecological sensitive area.
  - In December 2005, Battelle conducted soil verification sampling at four predetermined locations.
- 3. The site is located in a basin without designated municipal/domestic beneficial use.
  - Not applicable (see criterion 4).
- 4. The site is located in a basin with municipal/domestic beneficial use (outside a sensitive aquifer boundary).
  - Las Flores Creek is excepted from municipal beneficial use, but is reserved for agricultural, recreational, warm/cold fish habitat, wildlife habitat, and endangered species.

- The three production wells (10S/5W18E2, 10S/5W18M3, and 10S/5W18M4) located in the Las Flores watershed are clustered approximately 4.25 miles to the south of the site.
- 5. The dissolved hydrocarbon plume is not migrating.
  - Analytical results from 29 groundwater monitoring events have shown that the contaminant plume is stable and limited to the area beneath the Site 43286. Results from the two 2005 groundwater monitoring events showed no detections of targeted contaminants above cleanup goals.
- 6. No water wells, deeper drinking water aquifers, surface water, or sensitive receptors are likely to be impacted.
  - The three production wells (10S/5W18E2, 10S/5W18M3, and 10S/5W18M4) located in the Las Flores watershed are clustered approximately 4.25 miles to the south of the site, and are not threatened by Site 43286.
  - Las Flores Creek is the nearest surface water body and is located adjacent to Site 43286 with the main channel of the creek located approximately 200 ft east of the site. Findings of the 1999-2000 groundwater/surface water study determined that Site 43286 currently poses minimal threats to surface water and groundwater downgradient of the site.
- 7. The site presents no significant risk to human health.
  - Two 10,000-gallon gasoline USTs and one 550-gallon waste oil UST were removed from the Site in October 1993.
  - An IAS/SVE system was installed and operated by Battelle at Site 43286 from February 1999 through August 2000. The system was effective at removing 572 lb of petroleum hydrocarbons, which represents a 95.8 to 99.8% reduction in groundwater contamination.
  - Groundwater at the Site 43286 is currently impacted with COCs, but at levels below cleanup values. In 2005, benzene and toluene were not detected above reporting limits, and maximum detected concentrations of ethylbenzene, xylenes, and MTBE were 0.50 μg/L, 1.2 μg/L, and 4.5 μg/L, compared to cleanup goals of 680 μg/L, 1,750 μg/L, and 13 μg/L, respectively. These cleanup goals represent MCLs for drinking water, and Site 43286 groundwater achieved these goals.
- 8. The site presents no significant risk to the environment.
  - Current cleanup goals are based on concentrations protective of human health, however, by meeting these criteria the site is also protective of the environment. In addition, findings of the Las Flores Creek study conducted from 1999-2000 determined there is minimal to no threat of Las Flores Creek becoming impacted with target contaminants at levels above cleanup goals because Site 43286 groundwater has been remediated to these concentrations.

#### **Section 5.0: SUMMARY**

This Closure Report documents the mitigation process conducted by the discharger at Site 43286, better known as the 43 Area MWR Gas Station, including initial assessments, site monitoring, corrective action, and verification activities.

Verification soil and groundwater sampling have been conducted as part of the post-corrective action activities. Verification soil samples collected at Site 43286 indicated that detectable concentrations of target contaminants were only present in borings 43286-SV1 and 43286-SV4 but at concentrations below the established soil cleanup goals. Verification groundwater sampling was initiated immediately after the IAS/SVE system was shutdown on August 4, 2000 to evaluate the potential for contaminant rebound. No contaminant rebound has been reported from any site wells during ten subsequent groundwater monitoring events.

Las Flores Creek, which is located adjacent to Site 43286, is designated as a sensitive ecological receptor. A 1999-2000 creek study determined that there is minimal to no threat of Las Flores Creek becoming impacted with target contaminants originating from Site 43286 at levels above cleanup goals because site groundwater has been remediated to acceptable concentrations.


Extensive environmental activities have been conducted for more than a decade to support the remediation efforts at Site 43286. Though residual contamination remains at Site 43286, both soil and groundwater samples have conclusively shown that concentrations are below the cleanup criteria established for the site. In addition, an evaluation of Site 43286 shows that the current conditions meet the criteria established for "low-risk groundwater" sites. Based on this conclusive evidence, a recommendation for site closure with no further action is requested.


#### **Section 6.0: REFERENCES**


- Battelle. 1998a. Final Remediation Work Plan for the 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton Oceanside, California. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. July 31.
- Battelle. 1998b. *Modifications to Groundwater Monitoring Program at 43 Area Morale, Welfare, and Recreation Gas Station, Marine Corps Base Camp Pendleton, California*. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. February 6.
- Battelle. 1999. Summary Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton, Oceanside, California. Prepared for NFESC and SWDIV, Contract No. N47408-95-D-0730. January 14.
- Battelle. 2000a. Summary Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton, Oceanside, California. Prepared for NFESC and SWDIV, Contract No. N47408-95-D-0730. January 13.
- Battelle. 2000b. Surface Water Sampling and Analysis Plan for Las Pulgas Creek, Site 43286, Marine Corps Base Camp Pendleton, California. Prepared for NFESC and SWDIV under Contract No. N47408-95-D-0730. April.
- Battelle. 2001a. Summary Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for NFESC and SWDIV under Contract No. N47408-95-D-0730. January 25.
- Battelle. 2001b. Semiannual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for NFESC and SWDIV under Contract No. N47408-95-D-0730. July 5.
- Battelle. 2001c. Remedial Recommendations and Semiannual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for NFESC and SWDIV under Contract No. N47408-95-D-0730. October 16.
- Battelle. 2002. Annual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. October 15.
- Battelle. 2003a. Semiannual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. April 1.
- Battelle. 2003b. Work Plan for Soil Verification Sampling at Site 43286, Marine Corps Base Camp Pendleton. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. October 6.
- Battelle. 2004. Semiannual Groundwater Monitoring Report and Request for Closure, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. March.


- Battelle. 2005. Semiannual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation (MWR) Gas Station (Site 43286), Marine Corps Base Camp Pendleton. Prepared for Naval Facilities Engineering Command, Southwest, San Diego, CA. October 5.
- California Code of Regulations. 2000. Title 23, Division 3, Chapter 16. "California Underground Storage Tank Regulations." Available at: <a href="http://www.calregs.com">http://www.calregs.com</a>.
- California Code of Regulations. 2003. Title 22, Division 4, Chapter 15, Article 5.5, Table 64444-A. "Domestic Water Quality and Monitoring." Available at: <a href="http://www.calregs.com">http://www.calregs.com</a>. September.
- California State Water Resources Control Board. 1989. Leaking Underground Fuel Tank Field Manual: Guidelines for Site Assessment, Cleanup, and Underground Storage Tank Closure. Issued by the Leaking Underground Fuel Tank Force. October.
- CSWRCB, see California State Water Resources Control Board.
- DEH, see San Diego County Department of Environmental Health.
- International Technology Corporation. 1994. *Preliminary Results, Assessment Las Pulgas Gas Station, Area 43*. Project Note No. CLE-101-01F073-13-0007. February 7.
- IT Corp., see International Technology Corporation.
- OHM, see OHM Remediation Services, Inc.
- OHM/M&E, see OHM Remediation Services, Inc/Metcalf & Eddy, Inc.
- OHM Remediation Services, Inc. 1995. Final Site Assessment Report, 22 Area and 43 Area Gas Stations, Marine Corps Base Camp Pendleton, California. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. November.
- OHM Remediation Services, Inc. 1996. Final Remediation Work Plan, 22 Area and 43 Area Gas Stations, Marine Corps Base Camp Pendleton, California. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. March.
- OHM Remediation Services, Inc/Metcalf & Eddy, Inc. 1997. Petroleum Hydrocarbon Cleanup Demonstration Program, Expert Committee Briefing Package, 43 Area Morale, Welfare, and Recreation Gas Station, Marine Corps Base Camp Pendleton, California. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. May.
- OHM Remediation Services, Inc. 1997. Summary Groundwater Monitoring Report Third Quarter 1997: 43 Area Morale, Welfare and Recreation Gas Station, Marine Corps Base Camp Pendleton, California. Prepared for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. October 15.
- OHM Remediation Services, Inc/Metcalf & Eddy, Inc. 1998. Final Corrective Action Plan, 43 Area MWR Gas Station, Marine Corps Base Camp Pendleton, California. Prepared by OHM Remediation Services, Inc., and Metcalf and Eddy for Southwest Division, Naval Facilities Engineering Command, San Diego, CA. May 1.


- Regional Water Quality Control Board, San Diego Region. 1996. Regional Board Supplemental Instruction to State Water Board, December 8, 1995, Interim Guidance on Required Cleanup at Low-Risk Fuel Contaminated Sites. (Replaces the February 29, 1996 version.)
- Regional Water Quality Control Board, San Diego Region. 2002. RE: Remedial Recommendations and Semiannual Groundwater Monitoring Report, 43 Area Morale, Welfare, and Recreation Gas Station (Site 43286), Marine Corps Base Camp Pendleton, California, Dated October, 2001. Letter correspondence dated June 4.
- Regional Water Quality Control Board, San Diego Region. 2004. "Work Plan for Soil Verification Sampling at Site 43286, Marine Corps Base Camp Pendleton (Marine Corps Base Camp Pendleton Document Reference Number 5090.13c ENVSEC/414) (TSMC:50-2962.05:peass)." Letter correspondence dated April 7.
- Regional Water Quality Control Board, San Diego Region. 2005a. "Semiannual Groundwater Monitoring and Request for Closure, Site 43286, Marine Corps Base Camp Pendleton, California (TSMC: 50-2962.05:peass)." Letter correspondence dated January 11.
- Regional Water Quality Control Board, San Diego Region. 2005b. "Approval of Work Plan for Soil Verification Sampling at Site 43286, Marine Corps Base Camp Pendleton, California (SMC:50-2962.05:navrh)." Letter correspondence dated August 24.
- RWQCB, see Regional Water Quality Control Board, San Diego Region.
- San Diego County Department of Environmental Health. 2004. Site Assessment and Mitigation (SAM) Manual. San Diego, CA.




















Table 1. Summary of Site 43286 Environmental Activities

Date	Activity	Reference
October 1993	Removed two 10,000-gallon USTs and one 500-gallon UST.	Not available
1994	Initial Site Assessment - Nine borings (B1-B9) and three groundwater Monitoring wells (43286-MW01, 43286-MW02, and 43286-MW03) were installed and sampled. Investigation indicated that soil and groundwater at the site had been impacted by a release of fuel hydrocarbons.	IT Corp., 1994
August-September 1995	Additional Site Assessment - OHM installed and sampled one boring (B10) and one groundwater monitoring well (43286-MW04).	OHM, 1995
September-October 1995	Pilot Testing - OHM conducted aquifer pump testing, SVE, and DVE pilot-scale testing.	OHM, 1996
September 1995 - July 1997	Groundwater Monitoring - OHM conducted 7 consecutive quarterly groundwater monitoring events.	OHM, 1997
March-April 1997	Additional Site Assessment - OHM and M&E installed and sampled nine borings (HP-1 through HP-9) and four groundwater monitoring wells (43286-MW01A, 43286-MW05A, 43286-MW05B, and 43286-MW06), hand-augered borings into the Las Flores Creek embankment, and installed temporary stream channel piezometers in the Las Flores Creek.	OHM/M&E, 1997
February 1998 - July 2001	Groundwater Monitoring - Battelle conducted 16 consecutive quarterly groundwater monitoring events.	Battelle, 1999, 2000a, 2001a, 2001b, 2001c
May 1998	Final Corrective Action Plan (CAP) - The CAP recommended IAS/SVE for site remediation	OHM/M&E, 1998
July 1998	Final Remediation Work Plan - Battelle provided design, installation, and operation procedures for the IAS/SVE system.	Battelle, 1998a
December 1998 - January 1999	Field Design Testing - Battelle installed and conducted pilot testing for IAS/SVE feasibility and installed two additional groundwater monitoring wells (43286-MW07A and 43286-MW07B).	Not applicable
February 1999 – August 2000	IAS/SVE System Operation - Battelle implemented full-scale IAS/SVE system operation.	Not applicable
May 1999 – February 2000	Las Flores Creek surface water sampling - Surface water and groundwater sampling from installed piezometers and analysis was performed from the Las Flores Creek in order to evaluate the impact of site contaminants in this ecologically significant area.	Battelle, 2000b
August 2000	IAS/SVE System Shutdown - Battelle shut down the IAS/SVE system and initiated quarterly groundwater monitoring for one year to evaluate contaminant rebound.	Not Applicable
October 2001	Remedial Recommendation Report - Battelle documented groundwater monitoring and recommended that the IAS/SVE system be removed.	Battelle, 2001c
June 2002	IAS/SVE System Removal - RWQCB agreed to the removal of the IAS/SVE system and requested that groundwater monitoring be conducted semiannually for two years.	RWQCB, 2002
October 2002	Groundwater Monitoring - Battelle documented an annual monitoring event conducted in June 2002.	Battelle, 2002
October 2002	IAS/SVE Removal - Battelle removed the IAS/SVE system and abandoned IAS/SVE system wells.	Not applicable

Table 1. Summary of Site 43286 Environmental Activities (continued)

Date	Activity	Reference
October 2002	IAS/SVE Removal - Battelle removed the IAS/SVE system and abandoned IAS/SVE system wells.	Not applicable
July 2002 – January 2004	Groundwater Monitoring - Battelle conducted semiannual groundwater monitoring as recommended by the RWQCB.	Battelle, 2002, 2003a, 2004
October 2003	Soil Verification Sampling - Battelle issued the Work Plan for soil verification sampling.	Battelle, 2003b
March 2004	Site Closure Request - Battelle submitted a request for site closure and documented groundwater monitoring results.	Battelle, 2004
April 2004	Work Plan for Soil Verification Sampling - RWQCB questioned locations of proposed verification soil samples.	RWQCB, 2004
January 2005	Site Closure Request - In response to the request for site closure, RWQCB requested that groundwater monitoring be continued for two additional quarters in order to capture high groundwater levels resulting from heavy winter precipitation.	RWQCB, 2005a
April and July 2005	Groundwater Monitoring - Battelle conducted two additional quarters of groundwater monitoring to capture the high groundwater table.	Battelle, 2005
August 2005	Soil Verification Sampling - Battelle received approval to conduct verification soil sampling.	RWQCB, 2005b.
December 2005	Soil Verification Sampling - Battelle conducted soil verification sampling.	Not Applicable

Table 2. Site 43286 Soil and Groundwater Cleanup Goals

Constituent	Soil	Groundwater <sup>(a)</sup>
Benzene	ND SPLP or 0.1 mg/kg (b) total	1 μg/L
Toluene	ND SPLP or 15 mg/kg total	150 μg/L
Ethylbenzene	ND SPLP or 30 mg/kg total	300 μg/L
Total xylenes	ND SPLP or 175 mg/kg total	1,750 μg/L
MTBE	ND SPLP or 1.3 mg/kg total	13 μg/L

<sup>(</sup>a) Groundwater cleanup goals correspond to 2003 drinking water MCLs (California Code of Regulations, 2003).

<sup>(</sup>b) Assumes soil attenuation factor of 100.

 $<sup>\</sup>mu g/L = micrograms per liter.$ 

# APPENDIX A DOCUMENTATION OF IAS/SVE SYSTEM REMOVAL



PERMIT # W100816 A.P.N. #101-000-00 EST # H05939-095

# COUNTY OF SAN DIEGO DEPARTMENT OF ENVIRONMENTAL HEALTH LAND AND WATER QUALITY DIVISION

#### MONITORING WELL AND BORING CONSTRUCTION AND DESTRUCTION PERMIT

SITE NAME: SITE 43286

SITE ADDRESS: MARINE CORPS BASE, CAMP PENDLETON, CA 92055

PERMIT TO: DESTROY 18 AIR SPARCE WELLS, 5 SOIL VAPOR WELLS, 11 SOIL-GAS

#### MONITORING POINTS AND 9 PIEZOMETERS

PERMIT APPROVAL DATE: OCTOBER 11, 2002

PERMIT EXPINES ON: FEBRUARY 8, 2003

#### PERMIT CONDITIONS:

1. The 9 piezometers installed in February 1999 were not installed in compliance with the State Well Standards. None of these wells have any annular seals or proper surface completions. In consideration of the access limitations, these wells will have to be destroyed using the following procedures:

dolini.

- The well-casings must be excavated to a depth of 3 feet below the ground surface with a minimum of 6 inches around the casing depths.
- The well casings shall be cut to a depth of 1.5 feet below the ground surface.
- The interior of the well casings shall be filled to within 5 feet below the ground surface with a
  high-solids bentonite grout and allowed to set in accordance with the manufacturer's
  specifications.
- The interior of the well casings and the excavations around the casings from 5 feet to 1 foot of the ground surface shall be filled with a neat cement meeting the requirements of DWR Bulletin 74-90, Section 9, D, 2,a.
- The excavation, from 1 foot to the ground surface, can be backfilled with native soil.
- 2. All material within the original boreholes of the remaining wells, which includes the casings, filterpack and annular seals must be removed. The boreholes must be completely filled with an approved sealing material as specified in Department of Water Resources Bulletin 74-90.
- 3. All wash water must be contained and disposed of properly.






## MCB CAMP PENDLETON SPARGE WELL DESTRUCTION DIAGRAM 43286-SW1

43286-SW1DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069880.825
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/24/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed: 10/23/02	6207381.162
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.87 ft






## MCB CAMP PENDLETON SPARGE WELL DESTRUCTION DIAGRAM 43286-SW2

43286-SW2DSTRYD.CDR

Project #:	Site:		
		Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069957.277
Drilling Contractor:	Rig Type and Drilling Method:		
West Hazmat Drilling Corp.		Date Destroyed:10/22/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.34 ft
Ground Surface		Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs  Sealing Material: Type: Hydrated medium bentonite chips Amount: approx. 0.69 ft³  Material: Bentonite Grout t: approx. 6.81 ft³  Well Destruct - wellbox an completio - 1" well cas with 8" ho to 22.5 ft - 21 ft of 1" casing an schedule removed - borehole to bentonite	tion Procedure: d surface n broken up ing overdrilled illow stem augers bgs. schedule 40 PVC d 1 ft of 1" 40 PVC screen from borehole. backfilled with 6.81 ft³ grout
<b>N</b>			




Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2070000.210
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/25/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed: 10/22/02	6207394.706
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.65 ft
		Surface Seal Mate	rial:






43286-SW4DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069883.427
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 10/24/98 Date Destroyed:10/23/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.83 ft





Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069869.414
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 02/15/99 Date Destroyed:10/25/02	Easting: 6207377.388
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.49 ft






43286-SW6DSTRYD.CDR

		4320	30-24A0
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069883.722
Drilling Contractor:	Rig Type and Drilling Method:	,	Easting:
West Hazmat Drilling Corp.		Date Destroyed: 10/25/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.84 ft
Ground Surface	*/\	Surface Seal Mate Type: Concrete Amount: 0-1 ft bgs	
		Sealing Material: Type: Hydrated medium pentonite chips Amount: approx. 0.69 ft <sup>3</sup>	
	Type:	Material: Bentonite Grout t: approx. 5.93 ft³	
		- wellbox an completion of the	n broken up ing overdrilled illow stem augers bgs. schedule 40 PVC d 1 ft of 1" 40 PVC screen from borehole. backfilled with 5.93 ft <sup>3</sup> grout
		A R	ERED GEOLOGIST AND GOT AND GOT AND THE PROPERTY OF CALIFORNIA AND GOT
20.0 ft. Bottom of Borehole	Borehole Diamete	er: 8"	NOT TO SCALE




43286-SW7DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069885.8785
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 02/15/99 Date Destroyed:10/25/02	
Reviewed by: R. Janosy	Driller: Rick Hastings	Geologist: David Conner	Surface Elevation: 217.99 ft






Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069904.4244
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/15/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207396.6904
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.49 ft






Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069904.5640
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/15/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207411.6774
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.10 ft






43286-SW10DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069920.2709
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 02/16/99 Date Destroyed:10/23/02	Easting: 6207410.9487
Reviewed by: R. Janosy	Driller: Rick Hastings	Geologist: David Conner	Surface Elevation: 218.45 ft






Site:	Well Permit Number:	Northing:
MCB Camp Pendleton	W100816	2069919.5963
Rig Type and Drilling Method:	Date Installed: 02/16/99	Easting:
CME 75 HSA	Date Destroyed:10/23/02	6207423.0914
Driller:	Geologist:	Surface Elevation:
Rick Hastings	David Conner	218.39 ft
	MCB Camp Pendleton Rig Type and Drilling Method: CME 75 HSA Driller:	MCB Camp Pendleton W100816  Rig Type and Drilling Method: Date Installed: 02/16/99 CME 75 HSA Date Destroyed:10/23/02  Driller: Geologist:





43286-SW12DSTRYD.CDR


Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069934.7291
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/16/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207419.6999
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.41 ft






43286-SW13DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069942.6710
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/16/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/21/02	6207439.5197
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.58 ft






Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069959.3631
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 02/16/99 Date Destroyed:10/21/02	
Reviewed by: R. Janosy	Driller: Rick Hastings	Geologist: David Conner	Surface Elevation: 218.03 ft





43286-SW15DSTRYD.CDR


Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069957.5929
Drilling Contractor: West Hazmat Drilling Corp.	_	Date Installed: 02/17/99 Date Destroyed:10/21/02	_
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.70 ft





43286-SW16DSTRYD.CDR


Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069979.0415
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/17/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/21/02	6207458.5315
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.33 ft






43286-SW17DSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069952.3257
Drilling Contractor:  West Hazmat Drilling Corp.		Date Installed: 02/17/99 Date Destroyed:10/22/02	Easting: 6207418.6005
Reviewed by: R. Janosy	Driller: Rick Hastings	Geologist: David Conner	Surface Elevation: 218.27 ft





Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069970.1476
Drilling Contractor: West Hazmat Drilling Corp.	Rig Type and Drilling Method: CME 75 HSA	Date Installed: 02/17/99 Date Destroyed:10/21/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.29 ft





43286-43VEW1DSTRYD.CDR

MCB Camp Pendleton   W100816   NA   Easting:   Easting:   Surface Elevation:   NA   Easting:   Surface Seal Material:   Type: Concrete Amount: 0-1 ft bgs. (0.55 ft)   Sealing Material:   Type: Hydrated medium bentonite chips Amount: approx. 0.1.09 ft   Well Destruction Procedure:   - wellbox and surface   - wellbox		T		
Drilling Contractor: West Hazmat Drilling Corp. West Hazmat Drilling Corp. Reviewed by: R. Janosy  Driller: Rick Hastings  Driller: Rick Hastings  Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)  Sealing Material: Type: Bentonite Grout Amount: approx. 9.27 ft²  Well Destruction Procedure: - wellbox and surface completion broken up - 4* well casing overdilled with 10* hollow stem augers to 20.0 ft bgs 5.0 ft of 4* schedule 40 PVC casing and 15 ft of 4* schedule 40 PVC casing and 15 ft of 4* schedule 40 PVC casing and 15 ft of 4* schedule 40 PVC screen removed from borehole - borehole backfilled with 9.27 ft³ bentonite grout	Project #:	Site:	Well Permit Number:	Northing:
West Hazmat Drilling Corp.  CME 75 HSA  Date Destroyed: 10/25/02  NA  Surface Elevation:  David Conner  Surface Seal Material:  Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)  Sealing Material:  Type: Hydrated medium bentonite chips Amount: approx. 0.1.09 ft²  Well Destruction Procedure:  - wellbox and surface completion broken up - 4" well casing overdrilled with 10" hollow stem augers to 20.0 ft bgs 5.0 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 4" schedule 4" sch		<u> </u>		
Reviewed by: R. Janosy  Driller: Rick Hastings  David Conner  Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)  Sealing Material: Type: Hydrated medium bentonite chips Amount: approx. 0.1.09 ft²  Well Destruction Procedure: - wellbox and surface completion broken up - 4" well casing overdrilled with 10" hollow stem augers to 20.0 ft bgs 5.0 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC screen removed from borehole - borehole backfilled with 9.27 ft³ bentonite grout				_
R. Janosy  Rick Hastings  David Conner  NA  Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)  Sealing Material: Type: Hydrated medium benointe chips Amount: approx. 0.1.09 ft²  Sealing Material: Type: Bentonite Grout Amount: approx. 9.27 ft²  Well Destruction Procedure: - wellbox and surface completion broken up - 4" well casing overdrilled with 10" hollow stem augers to 20.0 ft bgs 5.0 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC creen removed from borehole borehole borehole borehole borehole abackfilled with 9.27 ft³ bentonite grout				
Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)  Sealing Material: Type: Hydrated medium bentonite chips Amount: approx. 0.1.09 ft²  Sealing Material: Type: Bentonite Grout Amount: approx. 0.1.09 ft²  Well Destruction Procedure: - wellbox and surface completion broken up - 4" well casing overdrilled with 10" hollow stem augers to 20.0 ft bgs 5.0 ft of 4" schedule 40 PVC screen removed from borehole - borehole backfilled with 9.27 ft² bentonite grout  MOT TO SCALE			1	
Type: Concrete Amount: 0-1 ft bgs. (0.55 ft²)    Sealing Material:   Type: Hydrated medium bentonite chips Amount: approx. 0.1.09 ft²   Well Destruction Procedure:   wellbox and surface   ormpletion broken up   of 4" well casing overdrilled with 10" hollow stem augers to 20.0 ft bgs.   of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC casing and 15 ft of 4" schedule 40 PVC screen removed from borehole   oberhole backfilled with 9.27 ft² bentonite grout	R. Janosy	RICK Hastings	David Conner	<u>NA</u>
- borehole backfilled with 9.27 ft³ bentonite grout  ERED GEOLOGIC # No. 7346  Expires 5/08  NOT TO SCALE	Ground Surface		Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs  Sealing Material: Type: Hydrated medium pentonite chips Amount: approx. 0.1.09 ft³  Material: Bentonite Grout t: approx. 9.27 ft³  Well Destruction - wellbox are completiced - 4" well case with 10" led to 20.0 ft or 5.0 ft of 4 casing are schedules.	erial: . (0.55 ft³)  etion Procedure: ad surface on broken up sing overdrilled hollow stem augers bgs. " schedule 40 PVC ad 15 ft of 4" 40 PVC screen
20.0 ft. Bottom of Borehole Borehole Diameter: 10 "			- borehole bentonite	backfilled with 9.27 ft <sup>3</sup> e grout  ERED GEOLOGIAN  ** No. 7346



13.5 ft. Bottom of Borehole

# MCB CAMP PENDLETON SOIL VAPOR EXTRACTION WELL DESTRUCTION DIAGRAM 43286-SVE1


	43286-SVE1			
Project #:	Site:	Well Permit Number:	Northing:	
G486031	MCB Camp Pendleton	W100816	2070012.9780	
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/24/98	Easting:	
West Hazmat Drilling Corp.		Date Destroyed:10/22/02	6207377.9209	
Reviewed by:	Driller:	Geologist:	Surface Elevation:	
R. Janosy	Rick Hastings	David Conner	219.01 ft	
Ground Surface	Sealing I Type: E	Well Destruct - well box ar completio - 2" well cas with 8" ho to 13.5 ft of 2" casing an schedule removed - borehole to bentonite	tion Procedure: and surface ri broken up ing overdrilled allow stem augers bgs. schedule 40 PVC d 10 ft of 2" 40 PVC screen from borehole. backfilled with 3.67 ft <sup>3</sup>	

**Borehole Diameter: 8"** 

**NOT TO SCALE** 



Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069949.7909
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/24/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/31/02	6207377.9511
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.91 ft






43286-SVE3DSTRYD.CDR

		40200-G¥	_•
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069962.5820
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/24/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/22/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.0 ft
Ground Surface	TY TEMENTER	Surface Seal Mate Type: Concrete Amount: 0-1 ft bgs.	
	Sealing I Type: It	Bentonite Grout	
	Amount	- well box ar completio - 2" well cas with 8" ho to 13.0 ft l - 3.0 ft of 2" casing an schedule removed to borehole be bentonite	n broken up ing overdrilled llow stem augers ogs. schedule 40 PVC d 10 ft of 2" 40 PVC screen from borehole. eackfilled with 3.49 ft <sup>3</sup> grout
		HE GOOD	# No. 7346  **Spires 5/03  **Cologist Rail  **OF CALIFORNIA
13.0 ft. Bottom of Borehole	Borehole Diamete	er: 8"	NOT TO SCALE



Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069988.0236
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/24/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/22/02	6207404.6615
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.07 ft






	I a	1	T.,
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	NA .
Drilling Contractor:	Rig Type and Drilling Method:		
West Hazmat Drilling Corp.		Date Destroyed:10/21/0	_
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	NA NA
Ground Surface	Sealing Type:	- well box complet - 2" well ca with 8" I to 14.0 f - 4.0 ft of casing a schedul remove	ction Procedure: and surface ion broken up using overdrilled hollow stem augers it bgs. 2" schedule 40 PVC and 10 ft of 2" e 40 PVC screen d from borehole. backfilled with 3.84 ft <sup>3</sup> e grout  ERED GEO  Who. 7346 Expires 5/03
14.0 ft. Bottom of Borehole	Borehole Diamete	er: 8"	NOT TO SCALE
NA = Not A	vailable		43286-SVE5DSTRYD.CDR



#### MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP1A

43286-MP1ADSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069978.396
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/26/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207383.098
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.80 ft






#### MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP1B

43286-MP1BDSTRYD.CDR

	43200-WIF 1B	
Site:	Well Permit Number:	Northing:
MCB Camp Pendleton	W100816	2069876.473
Rig Type and Drilling Method:	Date Installed: 10/25/98	Easting:
CME 75 HSA	Date Destroyed:10/23/02	6207386.813
Driller:	Geologist:	Surface Elevation:
Rick Hastings	David Conner	217.66 ft
	Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.35 ft³)	
	MCB Camp Pendleton Rig Type and Drilling Method: CME 75 HSA Driller:	Site:  MCB Camp Pendleton  Rig Type and Drilling Method: CME 75 HSA  Driller: Rick Hastings  Well Permit Number: W100816  Date Installed: 10/25/98 Date Destroyed:10/23/02  Geologist: David Conner  Surface Seal Mate Type: Concrete






#### MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP1C

43286-MP1CDSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069877.572
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/25/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/25/02	6207373.393
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	217.8 ft






## MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP2A

43286-MP2ADSTRYD.CDR


Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069958.633
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/26/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/21/02	6207409.343
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.34 ft





#### MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP2B

		43200-WIF 2D		
Project #:	Site:	Well Permit Number:	Northing:	
G486031	MCB Camp Pendleton	W100816	2069956.574	
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/26/98		
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/21/02	6207411.979	
Reviewed by:	Driller:	Geologist:	Surface Elevation:	
R. Janosy	Rick Hastings	David Conner	218.55 ft	
Ground Surface		Surface Seal Mate Type: Concrete Amount: 0-1 ft bgs		






#### MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP2C

43286-MP2CDSTRYD.CDR


Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069952.458
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/26/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207413.093
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.32 ft





## MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP2D

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069948.741
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/26/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/22/02	6207415.813
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.30 ft





# MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP3A

43286-MP3ADSTRYD.CDR

		I	
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2070002.116
Drilling Contractor:	Rig Type and Drilling Method:		Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/22/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.70 ft
Ground Surface	Rick Hastings    IIII = IIIII = IIII = IIII = IIII = IIII = IIII = IIII = IIIII = IIIII = IIII = III	Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs  Sealing Material: Type: Hydrated medium bentonite chips Amount: approx. 0.69 ft³  Material: Bentonite Grout t: approx. 5.24 ft³  Well Destruc - wellbox an completio - 2" well cas with 8" ho to 18.0 ft - 16.5 ft of 2 casing an schedule removed - vapor extr - borehole bentonite	tion Procedure: d surface on broken up ding overdrilled bllow stem augers bgs. 2" schedule 40 PVC d 1 ft of 2" 40 PVC screen from borehole raction points drilled out backfilled with 5.24 ft³
		OTATE.	OF CALIFORNIA
18.0 ft. Bottom of Borehole	Borehole Diamet	er: 8"	NOT TO SCALE



# MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP3B


43286-MP3BDSTRYD.CDR

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069996.62
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 10/25/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/22/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.49 ft
Ground Surface		Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs  Sealing Material: Type: Hydrated medium bentonite chips Amount: approx. 0.69 ft³  Material: Bentonite Grout tt approx. 5.24 ft³  Well Destruct - wellbox an completion - 2" well cas with 8" hot to 18.0 ft - 16.5 ft of 2 casing an schedule removed - vapor extroported bentonite	tion Procedure: d surface in broken up ing overdrilled fillow stem augers bgs. "schedule 40 PVC d 1 ft of 2" 40 PVC screen from borehole from borehole faction points drilled out backfilled with 5.24 ft <sup>3</sup> grout
18.0 ft. Bottom of Borehole	Borehole Diamet	er: 8"	NOT TO SCALE



# MCB CAMP PENDLETON **MONITORING POINT DESTRUCTION DIAGRAM** 43286-MP3C


Project #:	Site:	Well F	Permit Number:	Northing:
G486031	MCB Camp Pendleton	W10	0816	2069994.521
Drilling Contractor:	Rig Type and Drilling Method:	Date	Installed: 10/25/98	Easting:
West Hazmat Drilling Corp.	CME 75 HSA		Destroyed:10/22/02	
Reviewed by:	Driller:	Geol	ogist:	Surface Elevation:
R. Janosy	Rick Hastings	Dav	rid Conner	218.35 ft
		г		
			Surface Seal Mate	rial:





## MCB CAMP PENDLETON **MONITORING POINT DESTRUCTION DIAGRAM** 43286-MP4

Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069915.6112
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 2/16/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:10/23/02	6207413.936
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	218.35 ft





20.0 ft. Bottom of Borehole

# MCB CAMP PENDLETON MONITORING POINT DESTRUCTION DIAGRAM 43286-MP5

43286-MP5DSTRYD.CDR

		7020	JO-IVII J		
Project #:	Site:	Well Permit Number:	Northing:		
G486031	MCB Camp Pendleton	W100816	2069961.191		
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 2/17/99	Easting:		
West Hazmat Drilling Corp.		Date Destroyed:10/23/02			
Reviewed by:	Driller:	Geologist:	Surface Elevation:		
R. Janosy	Rick Hastings	David Conner	218.42 ft		
Surface Seal Material: Type: Concrete Amount: 0-1 ft bgs. (0.35 ft³)					
	Sealing Type:	Sealing Material: Type: Hydrated medium pentonite chips Amount: approx. 0.69 ft³  Material: Bentonite Grout t: approx. 5.93 ft³			
		- wellbox an completio - borehole d hollow ste - vapor extr	n broken up rilled out with 8" m augers to 22.0 ft bgs. action points drilled out backfilled with 5.93 ft <sup>3</sup>		
		A HED ON THE	# No. 7346 Dires 5/03  **OF CALIFORNIA		
20.0 ft. Bottom of Borehole	Borehole Diamet	er: 8"	NOT TO SCALE		

Borehole Diameter: 8"



# MCB CAMP PENDLETON PIEZOMETER DESTRUCTION DIAGRAM 43286-PZ01

43286-PZ01DSTRYD.CDR

		7020	0-PZU I
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069845.1869
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/09/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:11/04/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	201.64 ft
# No. 7346 Expires 5/63  **RED GEOLOGIST AND STATE OF CALIFORN  **RED GEOLOGIST AND STATE OF CALIFORN  ***EXPIRED FOR CAL	Type: nat Amount:	O-1 ft bgs.  Well Destruct - well casing of 3 ft. be (bgs) and casing - well casing bgs - interior of vertice bentonite ground sure interior of vertice and cast cem - excavation neat cem - excavation	tion Procedure: pexcavated to a depth low the ground surface 6 - 8 inches around the peut at a depth of 1.5 ft.  Well casing filled with grout to within 5 ft. of urface Well casing and n were backfilled with ent from 5 ft. to 1 ft. bgs backfilled from 1 ft. bgs surface with native soil




# MCB CAMP PENDLETON PIEZOMETER DESTRUCTION DIAGRAM 43286-PZ02

43286-PZ02DSTRYD.CDR

		7020	0-PZUZ
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069810.5660
Drilling Contractor:	Rig Type and Drilling Method:	Date Installed: 02/10/99	Easting:
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:11/04/02	6207451.3860
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	203.36 ft
### ### ##############################	Type: nat Amount:	Grout 0.02 ft³  Well Destruct - well casing of 3 ft. be (bgs) and casing - well casing bgs - interior of v bentonite ground su - interior of v excavation neat ceme - excavation	tion Procedure: I excavated to a depth low the ground surface 6 - 8 inches around the I cut at a depth of 1.5 ft. I well casing filled with grout to within 5 ft. of Irface I well casing and In were backfilled with ent from 5 ft. to 1 ft. bgs backfilled from 1 ft. bgs surface with native soil








43286-PZ04DSTRYD.CDR

G486031  Drilling Contractor:  West Hazmat Drilling Corp.  Reviewed by:  R. Janosy  Ground Surface (native soil)  """  """  ""  """  """  """  """  "	Driller: Rick Hastings  Sealings  Sealings	Surface S Type: nat Amount: (	Date Destroyed:11/04/0 Geologist:     David Conner  Seal Material: tive soil 0-1 ft bgs.	
Drilling Contractor: West Hazmat Drilling Corp. Reviewed by: R. Janosy  Ground Surface (native soil)	Rig Type and Drilling CME 75 H  Driller: Rick Hastings  Sealing  Sealing	Surface S Type: nat Amount: (	Date Installed: 02/10/9 Date Destroyed:11/04/0 Geologist: David Conner  Seal Material: tive soil 0-1 ft bgs.	9 Easting: 2 6207475.2866 Surface Elevation:
West Hazmat Drilling Corp.  Reviewed by: R. Janosy  Ground Surface (native soil)    The content of the content	CME 75 H  Driller: Rick Hastings  Sealing  Sealing	Surface S Type: nat Amount: (       =	Date Destroyed:11/04/0 Geologist: David Conner  Seal Material: tive soil 0-1 ft bgs.	2 6207475.2866 Surface Elevation:
Ground Surface (native soil)	Driller: Rick Hastings  Sealings  Sealings	Surface S Type: nat Amount: (	Date Destroyed:11/04/0 Geologist: David Conner  Seal Material: tive soil 0-1 ft bgs.	2 6207475.2866 Surface Elevation:
Ground Surface (native soil)	Rick Hastings	Type: nat Amount: (	David Conner  Seal Material: tive soil 0-1 ft bgs.	
Ground Surface (native soil)	Sealin	Type: nat Amount: (	Seal Material: tive soil 0-1 ft bgs.	198.57 ft
	=	Type: nat Amount: (	tive soil 0-1 ft bgs.	
=     = =     = =     = =     = =     =	Amo  Amo  Amo  Amo  Amo  Amo  Amo  Amo	Bentonite ount: approx.	Grout 0.01 ft³  Well Destru - well casi of 3 ft. t (bgs) ai casing - well casi bgs - interior of bentoni ground - interior of excavati neat ce - excavati	ction Procedure: ng excavated to a depth lelow the ground surface and 6 - 8 inches around the leng cut at a depth of 1.5 ft. If well casing filled with leng erout to within 5 ft. of surface If well casing and lion were backfilled with ment from 5 ft. to 1 ft. bgs and backfilled from 1 ft. bgs and surface with native soil



43286-PZ05DSTRYD.CDR





43286-PZ06DSTRYD.CDR

		4320	6-PZ06
Project #:	Site:	Well Permit Number:	Northing:
G486031	MCB Camp Pendleton	W100816	2069790.2115
Drilling Contractor:	Rig Type and Drilling Method		
West Hazmat Drilling Corp.	CME 75 HSA	Date Destroyed:11/04/02	
Reviewed by:	Driller:	Geologist:	Surface Elevation:
R. Janosy	Rick Hastings	David Conner	204.59 ft
Expires 6/03  Expires 6/03  Expires 6/03  Expires 6/03	Type: na Amount:	ent  Well Destruct  - well casing of 3 ft. be (bgs) and casing - well casing bgs - interior of v bentonite ground su - interior of v excavation neat cem - excavation	tion Procedure: gexcavated to a depth low the ground surface 6 - 8 inches around the gcut at a depth of 1.5 ft. well casing filled with grout to within 5 ft. of urface well casing and n were backfilled with ent from 5 ft. to 1 ft. bgs backfilled from 1 ft. bgs surface with native soil
=			NOT TO SCALE



43286-PZ07DSTRYD.CDR

Project #: G486031   MCB Camp Pendleton   MCB Cam
Drilling Contractor: West Hazmat Drilling Corp. Reviewed by: R. Janosy  Driller: Rick Hastings  David Conner  Surface Seal Material: Type: native soil Amount: 0.1 ft bgs.  Seal Material: Type: Bentonite Grout Amount: 0.21 ft's  Well Destruction Procedure: - well casing excavated to a depth of 3 ft. below the ground surface (bg) and 6 - 8 inches around the casing - well casing cut at a depth of 1.5 ft. bgs.  Inches Seal Material: Type: Amount: 0.21 ft's  Sealing Material: Type: No. 7346 Expires 3/38  Inches 3/38  Por CAURON  Procedure: - well casing cut at a depth of 1.5 ft. bgs interior of well casing and excavation were backfilled with neat cement from the casing and excavation were backfi
Reviewed by:   Driller:   Geologist:   David Conner   Surface Elevation:   200.37 ft
Reviewed by: R. Janosy    Driller: Rick Hastings   David Conner
R. Janosy  Rick Hastings  David Conner  200.37 ft  Surface Seal Material: Type: native soil Amount: 0-1 ft bgs.  Sealing Material: Type: neat cement Amount: 0.21 ft  Type: neat cement Amount: 0.21 ft  Type: neat cement Amount: 0.21 ft  Well Destruction Procedure: - well casing excavated to a depth of 3 ft. below the ground surface (bgs) and 6 - 8 inches around the casing - well casing cut at a depth of 1.5 ft. bgs - interior of well casing filled with bentonite grout to within 5 ft. of ground surface - interior of well casing and - excavation were backfilled with - excavation backfilled with - excavation backfilled from 1 ft. bgs - excavation backfilled from 1 ft. bgs - excavation backfilled from 1 ft. bgs - to ground surface with native soil  Type: native soil  Sealing Material: Type: neat cement Amount: 0.21 ft²  Type: neat cement - well casing cut at a depth of 1.5 ft. bgs - interior of well casing and - excavation were backfilled with - excavation backfilled from 1 ft. bgs - excavation backfilled from 1 ft. bgs - excavation backfilled from 1 ft. bgs - excavation were backfilled with - excavation were backfilled with - excavation were soil  Type: native soil  Well Destruction Procedure: - well casing excavated to a depth of 3 ft. below the ground surface (bgs) and 6 - 8 inches around the casing - well casing cut at a depth of 1.5 ft. bgs - interior of well casing and - excavation were backfilled with - excav
Surface Seal Material: Type: native soil Amount: 0-1 ft bgs.    Sealing Material:   Type: neat cement
Type: native soil Amount: 0-1 ft bgs.  Seal Material: Type: neat cement Amount: 0.21 ft amount: 0.21
Native soil



43286-PZ08DSTRYD.CDR

			4320	00-PZU0
Project #:	Site:		Well Permit Number:	Northing:
G486031	MCB Camp Pen	dleton	W100816	2069652.6398
Drilling Contractor:	Rig Type and Drilling	ng Method:	Date Installed: 02/11/99	Easting:
West Hazmat Drilling Corp.		SA	Date Destroyed:11/04/02	
Reviewed by:	Driller:		Geologist:	Surface Elevation:
R. Janosy	Rick Hastings		David Conner	196.46 ft
Expires 5/03  STATE OF CALLED  STATE OF CALLED	Sealing Type Amou	Type: nat Amount:	Grout 0.02 ft³  Well Destruc - well casing of 3 ft. be (bgs) and casing - well casing bgs - interior of bentonite ground si - interior of excavation neat cem - excavation	tion Procedure: g excavated to a depth low the ground surface 6 - 8 inches around the g cut at a depth of 1.5 ft. well casing filled with grout to within 5 ft. of urface well casing and on were backfilled with ent from 5 ft. to 1 ft. bgs a backfilled from 1 ft. bgs I surface with native soil



			4328	6-PZ09
Project #:	Site:		Well Permit Number:	Northing:
G486031	MCB Camp Pen	dleton	W100816	2069798.5699
Drilling Contractor:	Rig Type and Drilli	ng Method:	Date Installed: 02/12/99	Easting:
West Hazmat Drilling Corp.	CME 75 H	SA	Date Destroyed:11/04/02	
Reviewed by:	Driller:		Geologist:	Surface Elevation:
R. Janosy	Rick Hastings		David Conner	202.03 ft
Expires 5/03  Superior Section 1 Sec	Sealin Type Amo	Type: nat Amount:	Grout 0.02 ft³  Well Destruct - well casing of 3 ft. be (bgs) and casing - well casing bgs - interior of v bentonite ground su - interior of v excavation neat cem - excavation	tion Procedure: I excavated to a depth low the ground surface 6 - 8 inches around the I cut at a depth of 1.5 ft. I well casing filled with grout to within 5 ft. of Inface I casing and In were backfilled with ent from 5 ft. to 1 ft. bgs backfilled from 1 ft. bgs surface with native soil  NOT TO SCALE  43288-PZ09DSTRYD.CDR

# APPENDIX B DOCUMENTATION OF VERIFICATION SOIL SAMPLING



Billing Information: Name Gerald Tomokins	LABORATORY	Page #/	of
Address 505 King Avenue	Name ALAIA ANALY	THEAL	
City, State, Zip Columbus, OH 43201  Phone Number 614-424-4849 Fax 614-424-3667	Address SPARIS, NV	Analyses Required	
Client Name Battelle Memorial Institute	0.8	<del> </del>	
Address 505 King Avenue	PWS#	S./	NEDD
City, State, Zip Columbus, OH 43201	*	100 / 1/2 JICA JICA	
1 1	2	Solution of He All Man All And And All	рег: рег: С* <sup>г</sup>
Selow Lab ID Number	Sample Description	below # TT / W   Pb	70 01
1435 12/2 SO PMIDSIONER - 07	42201 - 547		10 RG
50	17200 CT	) .	12-3-05 long
05	1.	777	7
W 10/2 WA	]		2
		\	
		Alpha Analytical S	
		,	idiasa sading
		Security Seals?	NO NO
		Frozen Iqe?	
		1	ONI
ADDITIONAL INSTRUCTIONS:	Specific VOC Requirements (nlease snecifu)	20 Bob	PC # -
BIEX and	MIBE ANIN PRESENT	112) 274 (SII)	01anK" 330/
/ Bionature			
lby Mall	Print Name	Company	Date
Received by A. Charles	12	3	12-5-05 12:28
Received by			
Relinquished by			
Received by			
*Key: AQ - Aqueous SO - Soil WA - Waste	OT - Other **: L- Liter	V-Voa S-Soil Jar O-Orbo T-Tedlar	B-Brase D-Dioctio

nformation
=
Billing

Battele

505 King Avenue

Columbus, OH 43201

Battelle Memorial Institute 505 King Avenue

Columbus, OH 43201

Report Attention: Bob Janosy CC Report:

# CHAIN-OF-CUSTODY RECORD

AMENDED#2 1061

WorkOrder: BMI05120506

# Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21 Sparks, Nevada 89431-5778 TEL: (775) 355-1044 FAX: (775) 355-0406

EMail: janosyr@battelle.org TEL: (614) 424-7160 (614) 424-3667 FAX:

Report Due By: 5:00 PM On: 13-Dec-05
Ammandmand dua: 17/28/05 EDD Required: Yes

Sampled by: Client

14-Dec-05 Date Printed: ပ Cooler Temp : Client's COC #: none DOD QC Required: Final Rpt, MBLK, LCS, MS/MSD With Surrogates TO115-43286 Call Bob .: **q**of QC Level: DS3

Sample Remarks Requested Tests BTXE/MTBE SPLP (BTEX \_C MTBE) Voc\_w BTXE/MTBE \_C BTXE/MTBE BTXE/MTBE voc\_s TPH/P\_S GAS-C GAS-C GAS-C PWS# SUB TAT Collection No. of Bottles 0 0 0 0 ORG 12/02/05 14:35 12/02/05 13:30 12/02/05 11:35 12/02/05 12:35 Matrix Date SO SO SO SO BMI05120506-01A 43286-SV2 43286-SV3 43286-SV4 43286-SV1 Sample ID BMI05120506-02A BMI05120506-04A BMI05120506-03A Sample ID Alpha

No security seals, frozen ice. Saturday delivery, samples kept @4'c until log in 12-5-05. Temp Blank#5567 rec'd @4'c. Samples should be used as the control spike sample if possible. Level IV QC. Amended 12/12/05 per Randy- changed to 7 day TAT.: Amended 12/14/05 per Bob Janosy to add SPLP for BTEX & MTBE to -02. LE

Comments:

Company	Alpha Analytical, Inc.	
Print Name	hatricia Ednosa	
Signature	Latinia Eduara	
	Logged in by:	CLECT

12/14/05 M:32

Date/Time

The report for the analysis of the above samples is applicable only to those samples received by the laboratory with this COC. The liability of the laboratory is limited to the amount paid for the report. NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense. Matrix Type: AQ(Aqueous) AR(Air) SO(Soil) WS(Waste) DW(Drinking Water) OT(Other)

Bottle Type: L-Liter V-Voa S-Soil Jar O-Orbo T-Tedlar B-Brass P-Plastic OT-Other



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

### **ANALYTICAL REPORT**

Battelle Memorial Institute 505 King Avenue Columbus, OH 43201

Attn: Bob Janosy Phone: (614) 424-7160 Fax: (614) 424-3667 Date Received: 12/03/05

Job#: TO115-43286

### Volatile Organic Compounds (VOCs) EPA Method SW8260B

Client ID:	43286-SV1	Parameter	Concentration	Reporting Limit	Date Sampled	Date Analyzed
	43200-3 V I					
Lab ID:	BMI05120506-02A	Methyl tert-butyl ether (MTBE)	ND	0.50 μg/L	12/02/05	12/22/05
		Benzene	ND	0.50 μg/L	12/02/05	12/22/05
		Toluene	ND	0.50 μg/L	12/02/05	12/22/05
		Ethylbenzene	ND	0.50 μg/L	12/02/05	12/22/05
		Xylenes, Total	ND	0.50 μg/L	12/02/05	12/22/05
		Surr: 1,2-Dichloroethane-d4	92	%REC	12/02/05	12/22/05
		Surr: Toluene-d8	100	%REC	12/02/05	12/22/05
		Surr: 4-Bromofluorobenzene	82	%REC	12/02/05	12/22/05

This analysis was performed on an SPLP extract.

Note: The sample was analyzed 6 days past the 14-day hold time.

Roger Scholl

ND = Not Detected

Roger L. Scholl, Ph.D., Laboratory Director • • Randy Gardner, Laboratory Manager • • Walter Hinchman, Quality Assurance Officer

Sacramento, CA • (916) 366-9089 / Las Vegas, NV • (702) 281-4848 / info@alpha-analytical.com

12/27/05

**Report Date** 



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

Date: 13-Dec-05

**Bob Janosy** 

Battelle Memorial Institute

505 King Avenue Columbus, OH 43201 (614) 424-7160

**CASE NARRATIVE** 

Project:

TO115-43286

Work Order:

BMI05120506

Cooler	Temp:	°C
--------	-------	----

Alpha's Sample ID	Client's Sample ID	Matrix	
05120506-01A	43286-SV2	Soil	
05120506-02A	43286-SV1	Soil	
05120506-03A	43286-SV3	Soil	
05120506-04A	43286-SV4	Soil	

Enclosed please find the analytical results of the samples received by Alpha Analytical, Inc. under the above mentioned Work Order/Chainof-Custody.

Alpha Analytical, Inc. has a formal Quality Assurance/Quality Control program, which is designed to meet or exceed the EPA requirements. All relevant QC met quality assurance objectives for this project unless otherwise stated in the footnotes.

If you have any questions with regards to this report, please contact Randy Gardner, Project Manager, at (800) 283-1183.



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

### **ANALYTICAL REPORT**

Battelle Memorial Institute 505 King Avenue Columbus, OH 43201 Attn: Bob Janosy Phone: (614) 424-7160 Fax: (614) 424-3667 Date Received: 12/03/05

Job#: TO115/43286

Total Petroleum Hydrocarbons - Purgeable (TPH-P) EPA Method SW8015B/DHS LUFT Manual Volatile Organic Compounds (VOCs) EPA Method SW8260B

	Parameter	Concentration	Reporting	Date	Date
			Limit	Sampled	Analyzed
Client ID:	TPH Purgeable	ND	1.0 mg/Kg	12/02/05	12/09/05
43286-SV2	Methyl tert-butyl ether (MTBE)	ND	5.0 μg/Kg	12/02/05	12/09/05
Lab ID :	Benzene	ND	5.0 μg/Kg	12/02/05	12/09/05
BMI05120506-01A	Toluene	ND	5.0 μg/Kg	12/02/05	12/09/05
	Ethylbenzene	ND	5.0 μg/Kg	12/02/05	12/09/05
	m,p-Xylene	ND	5.0 μg/Kg	12/02/05	12/09/05
	o-Xylene	ND	5.0 μg/Kg	12/02/05	12/09/05
	Surr: 1,2-Dichloroethane-d4	98	%REC	12/02/05	12/09/05
	Surr: Toluene-d8	97	%REC	12/02/05	12/09/05
	Surr: 4-Bromofluorobenzene	94	%REC	12/02/05	12/09/05
Client ID :	TPH Purgeable	7.0	1.0 mg/Kg	12/02/05	12/07/05
43286-SV1	Methyl tert-butyl ether (MTBE)	ND	5.0 μg/Kg	12/02/05	12/07/05
Lab ID :	Benzene	ND	5.0 μg/Kg	12/02/05	12/07/05
BMI05120506-02A	Toluene	ND	5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	18	5.0 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	15	5.0 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND	5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	97	%REC	12/02/05	12/07/05
	Surr: Toluene-d8	95	%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98	%REC	12/02/05	12/07/05
Client ID:	TPH Purgeable	ND	1.0 mg/Kg	12/02/05	12/07/05
13286-SV3	Methyl tert-butyl ether (MTBE)	ND	5.0 μg/Kg	12/02/05	12/07/05
Lab ID :	Benzene	ND	5.0 μg/Kg	12/02/05	12/07/05
3MI05120506-03A	Toluene	ND	5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	ND	5.0 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	ND	5.0 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND	5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	98	%REC	12/02/05	12/07/05
	Surr: Toluene-d8	97	%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98	%REC	12/02/05	12/07/05



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

Client ID:	TPH Purgeable	39		2.0 mg/Kg	12/02/05	12/07/05
43286-SV4	Methyl tert-butyl ether (MTBE)	ND	V	10 μg/Kg	12/02/05	12/07/05
Lab ID:	Benzene	ND	V	10 μg/Kg	12/02/05	12/07/05
BMI05120506-04A	Toluene	ND	V	10 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	ND	V	10 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	ND	V	10 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND	V	10 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	97		%REC	12/02/05	12/07/05
	Surr: Toluene-d8	95		%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98		%REC	12/02/05	12/07/05

V = Reporting Limits were increased due to high concentrations of target analytes.

ND = Not Detected

Roger L. Scholl, Ph.D., Laboratory Director • • Randy Gardner, Laboratory Manager • • Walter Hinchman, Quality Assurance Officer Sacramento, CA • (916) 366-9089 / Las Vegas, NV • (702) 281-4848 / info@alpha-analytical.com

12/13/05

Report Date



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

Date: Work Order: OC Summary Report 13-Dec-05 05120506 Type: MBLK Test Code: EPA Method SW8260B Method Blank File ID: C:\HPCHEM\MS07\DATA\051207\05120709.D Batch ID: MS07S3657A Analysis Date: 12/07/2005 10:24 Sample ID: **MBLK MS07S3657A** Units: µg/Kg Run ID: MSD\_07\_051207B Prep Date: 12/07/2005 Analyte Result **PQL** SpkVal SpkRefVal %REC LowLimit HighLimit RPDRefVal %RPD(Limit) Qual Methyl tert-butyl ether (MTBE) ND Benzene 5 ND Toluene ND 5 Ethylbenzene ND 5 m,p-Xylene ND 5 o-Xvlene ND 5 Surr: 1,2-Dichloroethane-d4 197 200 98 68 119 Surr: Toluene-d8 191 200 96 84 116 Surr: 4-Bromofluorobenzene 199 200 99 72 118 Type: LCS **Laboratory Control Spike** Test Code: EPA Method SW8260B File ID: C:\HPCHEM\MS07\DATA\051207\05120710.D Batch ID: MS07S3657A Analysis Date: 12/07/2005 10:46 Sample ID: LCS MS07S3657A Units: µq/Kq Run ID: MSD 07 051207B Prep Date: 12/07/2005 Analyte Result **PQL** SpkVal SpkRefVal %REC LowLimit HighLimit RPDRefVal %RPD(Limit) Qual Methyl tert-butyl ether (MTBE) 410 400 152 10 102 42 Benzene 407 10 400 102 58 147 Toluene 403 400 58 148 10 101 Ethylbenzene 406 400 10 101 59 151 m,p-Xylene 415 400 60 10 104 155 o-Xylene 398 10 400 99.6 62 155 Surr: 1,2-Dichloroethane-d4 392 400 98 68 119 Surr: Toluene-d8 390 400 98 84 116 Surr: 4-Bromofluorobenzene 401 400 100 72 118 Sample Matrix Spike Type: MS Test Code: EPA Method SW8260B File ID: C:\HPCHEM\MS07\DATA\051207\05120720.D Batch ID: MS07S3657A Analysis Date: 12/07/2005 14:23 Sample ID: 05120246-01AMS Units: µg/Kg Run ID: MSD\_07\_051207B Prep Date: 12/07/2005 Analyte Result **PQL** SpkVal SpkRefVal %REC LowLimit HighLimit RPDRefVal %RPD(Limit) Qual Methyl tert-butyl ether (MTBE) 400 447 10 0 112 154 Benzene 393 10 400 98 30 151 0 Toluene 387 10 400 0 97 25 159 Ethylbenzene 402 400 27 10 0 100 161 m,p-Xylene 432 10 400 0 108 22 170 o-Xylene 408 22 10 400 171 O 102 Surr: 1,2-Dichloroethane-d4 385 400 96 68 119 Surr: Toluene-d8 393 400 98 84 116 Surr: 4-Bromofluorobenzene 443 400 111 72 118 Type: MSD Test Code: EPA Method SW8260B Sample Matrix Spike Duplicate File ID: C:\HPCHEM\MS07\DATA\051207\05120721.D Batch ID: MS07S3657A Analysis Date: 12/07/2005 14:45 Sample ID: 05120246-01AMSD Units: µg/Kg Run ID: MSD 07 051207B Prep Date: 12/07/2005 Analyte Result **PQL** SpkVal SpkRefVal %REC LowLimit HighLimit RPDRefVal %RPD(Limit) Qual Methyl tert-butyl ether (MTBE) 440 400 0 1.6(48) 10 110 23 154 447.3 Benzene 378 400 0 30 392.5 3.9(37) 10 94 151 Toluene 370 10 400 0 92 25 159 387.4 4.7(40) Ethylbenzene 378 10 400 0 95 27 161 401.7 6.0(39) m,p-Xylene 388 10 400 0 97 22 170 432.5 10.8(40) o-Xylene 382 10 400 0 96 22 407.9 6.5(41) 171 Surr: 1,2-Dichloroethane-d4 390 400 98 68 119 Surr: Toluene-d8 393 400 98 84 116 Surr: 4-Bromofluorobenzene 434 400 108 72 118

### Comments

Calculations are based off of raw (non-rounded) data. However, for reporting purposes, all QC data is rounded to three significant figures. Therefore, hand calculated values may differ slightly.




255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

<b>Date:</b> 13-Dec-05	OC S	lummar	y Report			<b>Work Order:</b> 05120506
Method Blank	Type: I	MBLK T	est Code: EPA Meti	hod SW80	015B/DHS LUFT M	anual
File ID: C:\HPCHEM\MS07\DATA\051207\0512070	9.D	Ва	atch ID: <b>MS07S365</b>	7B	Analysis Date:	12/07/2005 10:24
Sample ID: MBLK MS07S3657B Unit	s:mg/Kg	Run ID: MS	SD_07_051207B		Prep Date:	12/07/2005
Analyte	esult PQL	SpkVal	SpkRefVal %REC	LowLimit	HighLimit RPDRef	Val %RPD(Limit) Qual
TPH Purgeable NE	)	1	•			·
••	.197	0.2	98	68	119	
	.191	0.2	96	84	116	
Surr: 4-Bromofluorobenzene 0	.199	0.2	99	72	118	
Laboratory Control Spike	Туре: І	LCS Te	est Code: EPA Meti	nod SW80	15B/DHS LUFT Ma	anual
File ID: C:\HPCHEM\MS07\DATA\051207\0512072	2.D	Ва	atch ID: <b>MS07S365</b> 7	7B	Analysis Date:	12/07/2005 15:07
Sample ID: GLCS MS07S3657B Unit	s : <b>mg/Kg</b>	Run ID: MS	SD_07_051207B		Prep Date:	12/07/2005
Analyte R	esult PQL	SpkVal	SpkRefVal %REC	LowLimit	HighLimit RPDRef	Val %RPD(Limit) Qual
TPH Purgeable	19 :	2 16	119	60	153	
	.394	0.4	99	68	119	
	.377	0.4	94	84	116	
Surr: 4-Bromofluorobenzene 0	.396	0.4	99	72	118	
Sample Matrix Spike	Type: N	MS Te	est Code: EPA Meth	nod SW80	15B/DHS LUFT Ma	anual
File ID: C:\HPCHEM\MS07\DATA\051207\0512072	3.D	Ва	atch ID: MS07S3657	7B	Analysis Date:	12/07/2005 15:29
Sample ID: 05120246-01AGS Unit	s:mg/Kg	Run ID: MS	SD_07_051207B		Prep Date:	12/07/2005
	esult PQL			LowLimit	•	Val %RPD(Limit) Qual
TPH Purgeable	37.7	2 16	22 98	8	177	
	.392	0.4	98	68	119	
	.379	0.4	95	84	116	
Surr: 4-Bromofluorobenzene 0	.409	0.4	102	72	118	
Sample Matrix Spike Duplicate	Type: N	MSD Te	est Code: EPA Meth	od SW80	15B/DHS LUFT Ma	nual
File ID: C:\HPCHEM\MS07\DATA\051207\0512072	4.D	Ba	tch ID: <b>MS07S3657</b>	<b>′</b> B	Analysis Date:	12/07/2005 15:51
Sample ID: 05120246-01AGSD Unit	s : <b>mg/Kg</b>	Run ID: MS	SD_07_051207B		Prep Date:	12/07/2005
Analyte Ro	esult PQL	SpkVal	SpkRefVal %REC	LowLimit	HighLimit RPDRef\	Val %RPD(Limit) Qual
TPH Purgeable	36.7 2	2 16	22 92	8	177 37.74	4 2.8(45)
	.387	0.4	97	68	119	
	.377	0.4	94	84	116	
Surr: 4-Bromofluorobenzene 0	.421	0.4	105	72	118	

### Comments

Calculations are based off of raw (non-rounded) data. However, for reporting purposes, all QC data is rounded to three significant figures. Therefore, hand calculated values may differ slightly.





### LABORATORY DATA CONSULTANTS, INC.

7750 El Camino Real, Suite 2L Carlsbad, CA 92009 Phone: 760/634-0437 Fax: 760/634-0439

Battelle January 30, 2006

505 King Ave Columbus, OH 43201-2693 ATTN: Mr. Robert Janosy

SUBJECT: MCB Camp Pendleton, CTO 115, Data Validation

Dear Mr. Janosy,

Enclosed are the final validation reports for the fractions listed below. This SDG was received on January 25, 2006. Attachment 1 is a summary of the samples that were reviewed for each analysis.

### **LDC Project # 14559:**

SDG # Fraction

BMI05120506 Volatiles, TPH as Purgeables

The data validation was performed under EPA Level III and IV guidelines. The analyses were validated using the following documents, as applicable to each method:

- USEPA, Contract Laboratory Program National Functional Guidelines for Organic Data Review, October 1999
- EPA SW 846, Third Edition, Test Methods for Evaluating Solid Waste, update 1, July 1992; update IIA, August 1993; update II, September 1994; update IIB, January 1995; update III, December 1996; update IIIA, April 1998

Please feel free to contact us if you have any questions.

Sincerely,


Erlinda T. Rauto

Operations Manager/Senior Chemist

	Attachment 1																																				
	10/90	LDC #14559 (Battelle-Columbus OH / MCB Camp Pendleton, CTO 115)																																			
LDC	SDG#	DATE REC'D	(3) DATE DUE	B1 (82	TEX 60B)	ВТ	EX (SOB)	TP (80	H-P (15)																												
Matrix	c: Water/Soil		T	_	s	W	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s	w	s
Α	BMI05120506	01/25/06				0			3		_								<u> </u>									<u> </u>				$\square$					L
A	BMI05120506	01/25/06	02/15/06	0	1	0	0	0	1																							H			$\vdash$		$\vdash$
$\dashv$				_															_						Щ												$\vdash$
$\dashv$				$\vdash$	-															_												$\dashv$					$\vdash$
$\dashv$					┢	_																					-									$\dashv$	$\vdash$
士																																					
_				_																																$\Box$	
-						-											Н					_								_		$\dashv$		$\dashv$	$\dashv$	$\dashv$	$\vdash$
					_		Н																													$\dashv$	_
$\dashv$														$\dashv$			H															$\dashv$			$\dashv$		
																																			$\Box$	$\Box$	
$\dashv$				-			-			$\dashv$			-	$\dashv$																	$\dashv$	-		$\dashv$		$\dashv$	
																																$\exists$	$\dashv$		$\neg$	$\dashv$	_
																																				$\Box$	
-+					-	Н					$\dashv$		-	_	$\dashv$																	$\dashv$			$\rightarrow$	$\dashv$	
$\exists$																																					
																																$\Box$	$\Box$	$\Box$	$\Box$	$\Box$	
$\dashv$							$\dashv$			$\dashv$		$\dashv$	$\dashv$	-	-								_		$\dashv$			Н			$\dashv$	$\dashv$	{	$\dashv$	$\dashv$	$\dashv$	_
				_																													_	_		$\dashv$	
otal	B/LR	- in		0	4	0	1	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	9

### MCB Camp Pendleton, CTO 115 Data Validation Reports LDC# 14559

Volatiles



### Laboratory Data Consultants, Inc. **Data Validation Report**

Project/Site Name:

Camp Pendleton, CTO 115

**Collection Date:** 

December 2, 2005

LDC Report Date:

January 27, 2006

Matrix:

Soil

Parameters:

Volatiles

Validation Level:

EPA Level III & IV

Laboratory:

Alpha Analytical, Inc.

Sample Delivery Group (SDG): BMI05120506

Sample Identification

43286-SV2

43286-SV1

43286-SV3

43286-SV4\*\*

43286-SV1 SPLP

<sup>\*\*</sup>Indicates sample underwent EPA Level IV review

### Introduction

This data review covers 5 soil samples listed on the cover sheet including dilutions and reanalysis as applicable. The analyses were per EPA SW 846 Method 8260B for Volatiles.

This review follows a modified outline of the USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review (October 1999) as there are no current guidelines for the method stated above.

A qualification summary table is provided at the end of this report if data has been qualified. Flags are classified a P (protocol) or A (advisory) to indicate whether the flag is due to a laboratory deviation from a specified protocol or is of technical advisory nature.

Blank results are summarized in Section V.

Field duplicates are summarized in Section XVI.

Samples indicated by a double asterisk on the front cover underwent a EPA Level IV review. A EPA Level III review was performed on all of the other samples. Raw data were not evaluated for the samples reviewed by Level III criteria since this review is based on QC data.

The following are definitions of the data qualifiers:

- U Indicates the compound or analyte was analyzed for but not detected at or above the stated limit.
- J Indicates an estimated value.
- R Quality control indicates the data is not usable.
- N Presumptive evidence of presence of the constituent.
- UJ Indicates the compound or analyte was analyzed for but not detected. The sample detection limit is an estimated value.
- A Indicates the finding is based upon technical validation criteria.
- P Indicates the finding is related to a protocol/contractual deviation.
- None Indicates the data was not significantly impacted by the finding, therefore qualification was not required.

### I. Technical Holding Times

All technical holding time requirements were met

The chain-of-custodies were reviewed for documentation of cooler temperatures. All cooler temperatures met validation criteria.

### II. GC/MS Instrument Performance Check

Instrument performance was checked at 12 hour intervals.

All ion abundance requirements were met.

### III. Initial Calibration

Initial calibration was performed using required standard concentrations.

Percent relative standard deviations (%RSD) were less than or equal to 15.0% for each individual compound and less than or equal to 30.0% for calibration check compounds (CCCs).

In the case where %RSD was greater than 15.0%, the laboratory used a calibration curve to evaluate the compound. All coefficients of determination ( $r^2$ ) were greater than or equal to 0.990.

For the purposes of technical evaluation, all compounds were evaluated against the 30.0% (%RSD) National Functional Guideline criteria. Unless noted above, all compounds were within the validation criteria.

Average relative response factors (RRF) for all volatile target compounds were within method and validation criteria.

### IV. Continuing Calibration

Continuing calibration was performed at the required frequencies.

Percent differences (%D) between the initial calibration RRF and the continuing calibration RRF were within the method criteria of less than or equal to 20.0% for calibration check compounds (CCCs).

For the purposes of technical evaluation, all compounds were evaluated against the 25.0% (%D) National Functional Guideline criteria. Unless noted above, all compounds were within the validation criteria.

All of the continuing calibration RRF values were within method and validation criteria.

### V. Blanks

Method blanks were reviewed for each matrix as applicable. No volatile contaminants were found in the method blanks.

### VI. Surrogate Spikes

Surrogates were added to all samples and blanks as required by the method. All surrogate recoveries (%R) were within QC limits.

### VII. Matrix Spike/Matrix Spike Duplicates

The laboratory has indicated that there were no matrix spike (MS) and matrix spike duplicate (MSD) analyses specified for the samples in this SDG, and therefore matrix spike and matrix spike duplicate analyses were not performed for this SDG.

### VIII. Laboratory Control Samples (LCS)

Laboratory control samples were reviewed for each matrix as applicable. Percent recoveries (%R) were within QC limits.

### IX. Regional Quality Assurance and Quality Control

Not applicable.

### X. Internal Standards

All internal standard areas and retention times were within QC limits.

### XI. Target Compound Identifications

All target compound identifications were within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

### XII. Compound Quantitation and CRQLs

All compound quantitation and CRQLs were within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

### XIII. Tentatively Identified Compounds (TICs)

Tentatively identified compounds were not reported by the laboratory.

### XIV. System Performance

The system performance was within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

### XV. Overall Assessment of Data

Data flags are summarized at the end of this report if data has been qualified.

### XVI. Field Duplicates

No field duplicates were identified in this SDG.

### XVII. Field Blanks

No field blanks were identified in this SDG.

Camp Pendleton, CTO 115 Volatiles - Data Qualification Summary - SDG BMI05120506

No Sample Data Qualified in this SDG

Camp Pendleton, CTO 115 Volatiles - Laboratory Blank Data Qualification Summary - SDG BMI05120506

No Sample Data Qualified in this SDG



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

### **ANALYTICAL REPORT**

Battelle Memorial Institute 505 King Avenue Columbus, OH 43201 Attn: Bob Janosy Phone: (614) 424-7160 Fax: (614) 424-3667 Date Received: 12/03/05

Job#: TO115-43286

Volatile Organic Compounds (VOCs) EPA Method SW8260B

		Parameter	Concentration	Reporting Limit	Date Sampled	Date Analyzed
Client ID:	43286-SV1					
Lab ID:	BMI05120506-02A	Methyl tert-butyl ether (MTBE)	ND 🚺	0.50 μg/L	12/02/05	12/22/05
		Benzene	ND	0.50 μg/L	12/02/05	12/22/05
		Toluene	ND	0.50 μg/L	12/02/05	12/22/05
		Ethylbenzene	ND	0.50 μg/L	12/02/05	12/22/05
		Xylenes, Total	ND J	0.50 μg/L	12/02/05	12/22/05
		Surr: 1,2-Dichloroethane-d4	92	%REC	12/02/05	12/22/05
		Surr: Toluene-d8	100	%REC	12/02/05	12/22/05
		Surr: 4-Bromofluorobenzene	82	%REC	12/02/05	12/22/05

This analysis was performed on an SPLP extract.

Note: The sample was analyzed 6 days past the 14-day hold time.

ND = Not Detected

Roger Scholl Kandys Saulien Dalter Arthur Roger L. Scholl, Ph.D., Laboratory Director · Randy Gardner, Laboratory Manager · · Walter Hinchman, Quality Assurance Officer Sacramento, CA · (916) 366-9089 / Las Veges, NV · (702) 281-4848 / info@alpha-analytical.com

12/27/05

Report Date

120/06



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

### **ANALYTICAL REPORT**

Battelle Memorial Institute 505 King Avenue Columbus, OH 43201 Attn: Bob Janosy Phone: (614) 424-7160 Fax: (614) 424-3667 Date Received: 12/03/05

Job#:

TO115/43286

Total Petroleum Hydrocarbons - Purgeable (TPH-P) EPA Method SW8015B/DHS LUFT Manual Volatile Organic Compounds (VOCs) EPA Method SW8260B

	Parameter	Concentration	Reporting	Date	Date
			Limit	Sampled	Analyzed
Client ID:	- TPH Purgsable	ND-	1.0 mg/Kg	12/02/05	12/09/05
43286-SV2	Methyl tert-butyl ether (MTBE)	ND M	5.0 μg/Kg	12/02/05	12/09/05
Lab ID:	Benzene	ND	5.0 μg/Kg	12/02/05	12/09/05
BMI05120506-01A	Toluene	ND	5.0 μg/Kg	12/02/05	12/09/05
	Ethylbenzene	ND	5.0 μg/Kg	12/02/05	12/09/05
	m,p-Xylene	ND	5.0 μg/Kg	12/02/05	12/09/05
	o-Xylene	ND 🗸	. 5.0 μg/Kg	12/02/05	12/09/05
	Surr: 1,2-Dichloroethane-d4	98	%REC	12/02/05	12/09/05
	Surr: Toluene-d8	97	%REC	12/02/05	12/09/05
	Surr: 4-Bromofluorobenzene	94	%REC	12/02/05	12/09/05
Client ID:	-TPH Purgeable	7.0	1.0 mg/Kg	12/02/05	12/07/05
43286-SV1	Methyl tert-butyl ether (MTBE)	ND L	5.0 μg/Kg	12/02/05	12/07/05
Lab ID :	Benzene	ND	5.0 μg/Kg	12/02/05	12/07/05
BMI05120506-02A	Toluene	ND ↓	5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	18	5.0 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	15	5.0 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND L	5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	97	%REC	12/02/05	12/07/05
	Surr: Toluene-d8	95	%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98	%REC	12/02/05	12/07/05
Client ID:	-TPH Purgeable	ND ND	1.0 mg/Kg	12/02/05	12/07/05
43286-SV3	Methyl tert-butyl ether (MTBE)	ND 🗸	5.0 μg/Kg	12/02/05	12/07/05
Lab ID:	Benzene	ND	5.0 μg/Kg	12/02/05	12/07/05
BMI05120506-03A	Toluene	ND	5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	ND	5.0 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	ND	5.0 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND 1	5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	98	%REC	12/02/05	12/07/05
	Surr: Toluene-d8	97	%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98	%REC	12/02/05	12/07/05

M. 120/04



255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

Client ID:	TPH Purgeable	39	•	2.0 mg/Kg	12/02/05	12/07/05	
43286-SV4	Methyl tert-butyl ether (MTBE)	ND	νŲ	10 μg/Kg	12/02/05	12/07/05	
Lab ID:	Benzene	ND	v	10 μg/Kg	12/02/05	12/07/05	
BMI05120506-04A	Toluene	ND	v	10 μg/Kg	12/02/05	12/07/05	
	Ethylbenzene	ND	v	10 μg/Kg	12/02/05	12/07/05	
	m,p-Xylene	ND	v	10 μg/Kg	12/02/05	12/07/05	
	o-Xylene	ND	v J	10 μ <b>g/Kg</b>	12/02/05	12/07/05	
	Surr: 1,2-Dichloroethane-d4	97		%REC	12/02/05	12/07/05	
	Surr: Toluene-d8	95		%REC	12/02/05	12/07/05	
	Surr: 4-Bromofluorobenzene	98		%REC	12/02/05	12/07/05	

V = Reporting Limits were increased due to high concentrations of target analytes.

ND = Not Detected

Roger Scholl Kandy Salmer Water Hinchman, Quality Assurance Officer Sacramento, CA • (916) 366-9089 / Las Vegas, NV • (702) 281-4848 / info@alpha-analytical.com

Report Date

1/20/04

VALIDATION COMPLETENESS MODESULET	20/27/06
VALIDATION COMPLETENESS WORKSHEET	Date: <u>// 27/</u> 00
Level III/IV	Page: <u>/</u> pf/
<b>)</b> .	Reviewer:
	2nd Reviewer:
	VALIDATION COMPLETENESS WORKSHEET Level III/IV

METHOD: GC/MS Volatiles (BTEX)(EPA SW 846 Method 8260B)

The samples listed below were reviewed for each of the following validation areas. Validation findings are noted in attached validation findings worksheets.

	Validation Area		Comments
I.	Technical holding times	Δ	Sampling dates:  7/2/05
H.	GC/MS Instrument performance check	Δ	, ,
III.	Initial calibration	A	% PSP (2 20.99U
IV.	Continuing calibration	Δ	,
V.	Blanks	Δ	
VI.	Surrogate spikes	Α	
VII.	Matrix spike/Matrix spike duplicates	2	chent specifical
VIII.	Laboratory control samples	Α	Les
IX.	Regional Quality Assurance and Quality Control	N	
X.	Internal standards	Α	
XI.	Target compound identification	A	Not reviewed for Level III validation.
XII.	Compound quantitation/CRQLs	A	Not reviewed for Level III validation.
XIII.	Tentitatively identified compounds (TICs)	2	Not reviewed for Level III validation. not sepo / tes
XIV.	System performance	Δ	Not reviewed for Level III validation.
XV.	Overall assessment of data	<b>A</b>	
XVI.	Field duplicates	N,	
XVII.	Field blanks	N	

Note: A = Acceptable

ND = No compounds detected D = Duplicate

N = Not provided/applicable

R = Rinsate

TB = Trip blank

SW = See worksheet

FB = Field blank

EB = Equipment blank

Validated Samples: \*\* Indicates sample underwent Level IV validation


	SOIL							
71	43286-SV2	11	MBIK	M50753	<b>2</b> 15	1A	31	
21	43286-SV1	12 2		M S07W1:			32	
3	43286-SV3	13			23		33	
4	43286-SV4**	14			24		34	
5 <b>2</b>	43286-SV1 SPLP	15			25		35	
6		16			26		36	
7		17			27		37	
8		18			28		38	
9		19			29		39	
10		20			30		40	

### LDC #: 14559A) SDG #: BBBM 105 2050 6


### VALIDATION FINDINGS CHECKLIST

Method: Volatiles (EPA SW 846 Method 8260B)

Validation Area	Yes	No	NA	Findings/Comments
1. Technical holding times	163	NO	INA	Tittuing 500 miletta
All technical holding times were met.	./			
Cooler temperature criteria was met.	/	1		
II. GC/MS Instrument performance check				
Were the BFB performance results reviewed and found to be within the specified criteria?	V			
Were all samples analyzed within the 12 hour clock criteria?	V			
III. Initial calibration				
Did the laboratory perform a 5 point calibration prior to sample analysis?	V			
Were all percent relative standard deviations (%RSD) and relative response factors (RRF) within method criteria for all CCCs and SPCCs?	/			
Was a curve fit used for evaluation?	V	,		
Did the initial calibration meet the curve fit acceptance criteria of > 0.990?	1			
Were all percent relative standard deviations (%RSD) < 30% and relative response factors (RRF) > 0.05?	V			
IV. Continuing calibration	T -		<u>.</u>	
Was a continuing calibration standard analyzed at least once every 12 hours for each instrument?	0	,		
Were all percent differences (%D) and relative response factors (RRF) within method criteria for all CCCs and SPCCs?	_			
Were all percent differences (%D) ≤ 25% and relative response factors (RRF) ≥ 0.05?	/			
V. Blanks				
Was a method blank associated with every sample in this SDG?	/			
Was a method blank analyzed at least once every 12 hours for each matrix and concentration?		•		
Was there contamination in the method blanks? If yes, please see the Blanks validation completeness worksheet.				
VI. Surrogate spikes			<u>L</u>	
Were all surrogate %R within QC limits?	/			
If the percent recovery (%R) for one or more surrogates was out of QC limits, was a reanalysis performed to confirm samples with %R outside of criteria?				
VII. Matrix spike/Matrix spike duplicates	,			
Were: a matrix spike (MIS) and matrix spike duplicate (MSD) analyzed for each matrix in this SDG? If no, indicate which matrix does not have an associated MS/MSD. Suil / Water.				
Was a MS/MSD arallyzed every 20 samples of each matrix?				
Were the MS/MSD percent recoveries (%R) and the relative percent differences (RPD) within the QC limits?			/	
VIU. Laboratory control samples			-	Control of the State of the Sta
Was an LCS analyzed for this SDG?	-			



### VALIDATION FINDINGS CHECKLIST



Validation Area	Yes	No	NA	Findings/Comments
Was an LCS analyzed per analytical batch?	/	-		
Were the LCS percent recoveries (%R) and relative percent difference (RPD) within the QC limits?		Carrows 111 11 11 11		Company of the compan
IX. Regional Quality Assurance and Quality Control		lico.		
Were performance evaluation (PE) samples performed?			-	
Were the performance evaluation (PE) samples within the acceptance limits?		Second like		
X. Internal standards				
Were internal standard area counts within -50% or +100% of the associated calibration standard?	/	_		
Were retention times within ± 30 seconds of the associated calibration standard?	/			
XI. Target compound Identification	JI .		2,401	A CONTRACT TO SERVER THE SERVER S
Were relative retention times (RRT's) within ± 0.06 RRT units of the standard?			/	
Did compound spectra meet specified EPA "Functional Guidelines" criteria?				
Were chromatogram peaks verified and accounted for?				
XII. Compound quantitation/CRQLs	I T			
Were the correct internal standard (IS), quantitation ion and relative response factor (RRF) used to quantitate the compound?			/	
Were compound quantitation and CRQLs adjusted to reflect all sample dilutions and dry weight factors applicable to level IV validation?		_		
XIII. Tentatively identified compounds (TICs)				The state of the s
Were the major ions (> 10 percent relative intensity) in the reference spectrum evaluated in sample spectrum?				
Were relative intensities of the major ions within ± 20% between the sample and the reference spectra?			_	
Did the raw data indicate that the laboratory performed a library search for all required peaks in the chromatograms (samples and blanks)?			_	
XIV. System performance				American State of the Control of the
System performance was found to be acceptable.	/	1		
XV. Overall assessment of data				1000 A 2000 A
Overall assessment of data was found to be acceptable.	/	•		
XVI. Field duplicates				
Field duplicate pairs were identified in this SDG.		_		
Target compounds were detected in the field duplicates.				
XVII. Field blanks				
Field blanks were identified in this SDG.		/	<b>'</b>	
Target compounds were detected in the field blanks.				

LDC #: 14599 A )
SDG #: BM105120506

# VALIDATION FINDINGS WORKSHEET Initial Calibration Calculation Verification

Page:_	
Reviewer:_	77
2nd Reviewer:_	2
_	

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The Relative Response Factor (RRF), average RRF, and percent relative standard deviation (%RSD) were recalculated for the compounds identified below using the

RRF =  $(A_y)(C_h)/(A_h)(C_y)$ average RRF = sum of the RRFs/number of standards %RSD = 100 \* (S/X)

 $A_x$  = Area of compound,

 $A_k$  = Area of associated internal standard  $C_k$  = Concentration of internal standard

 $C_x$  = Concentration of compound,

S = Standard deviation of the RRFs

X = Mean of the RRFs

				Reported	Recalculated	Reported	Recalculated	Reported	Recalculated
#	Standard ID	Calibration Date	Compound (Reference Internal Standard)	RRF (32 std)	RRF	Average RRF (Initial)	Average RRF (initial)	%RSD	%RSD
1	ICAL	148/05	Methylene chloride (1st internal standard)	4.996 x10"	4.996 \$10	4.367×10	4-3767410	13.8	13.8
			Trichlorethene (2nd internal standard)	3.542	3.542	3.711	3.711	7-3	7-3
			Toluene (3rd internal standard)						
2			Methylene chloride (1st internal standard)	·					
			Trichlorethene (2nd Internal standard)						
			Toluene (3rd internal standard)						
3			Methylene chloride (1st internal standard)						
			Trichlorethene (2nd internal standard)						
			Toluene (3rd internal standard)						<del></del>
4			Methylene chloride (1st internal standard)						
			Trichlorethene (2nd internal standard)						
			Toluene (3rd internal standard)						

Comments: Refer to Initial Calibration findings worksheet for list of qualifications and associated samples when reported results do not agree within 10.0% of the

LDC #: 14 559A | SDG #: BM | OS 120 506

### VALIDATION FINDINGS WORKSHEET Continuing Calibration Results Verification

	Page:_	/of	1
	Reviewer:	A	
2nd	Reviewer:	2	
	-		

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The percent difference (%D) of the initial calibration average Relative Response Factors (RRFs) and the continuing calibration RRFs were recalculated for the compounds identified below using the following calculation:

% Difference = 100 \* (ave. RRF - RRF)/ave. RRF

-

Where: ave. RRF = initial calibration average RRF

 $RRF = (A_x)(C_{la})/(A_{la})(C_x)$ 

RRF = continuing calibration RRF A<sub>v</sub> = Area of compound,

A<sub>k</sub> = Area of associated internal standard

C<sub>x</sub> = Concentration of compound,

C<sub>L</sub> = Concentration of internal standard

					Reported	Recalculated	Reported	Recalculated
#	Standard ID	Calibration Date	Compound (Reference internal Standard)	Average RRF (initial)	RRF (CC)	RRF (CC)	%D	%D
1	05 120106	12/7/05	MIST Methylene chloride (1st internal standard)	0.437	0.421	0.421	3.7	3.7
	cev	•	Trichierethene (2nd internal standard)	3.711	3825	3.82	3.)	3.1
			Toluene (3rd internal standard)					
2			Methylene chloride (1st internal standard)					
			Trichlorethene (2nd internal standard)					
			Toluene (3rd internal standard)					
3	•		Methylene chloride (1st Internal standard)					
			Trichlorethene (2nd internal standard)					
			Toluene (3rd internal standard)	. " .				
4	·		Methylene chioride (1st internal standard)					
			Trichlorethene (2nd internal standard)					
			Toluene (3rd internal standard)					

Comments:	Refer to	Continuing	Calibration findings	worksheet fo	r list of	qualifications	s and	associated sam	ples when	reported	results (	do not	<u>agree within</u>	10.0% of the	<u>1e</u>
recalculated	results.													•	
										5.45					

LDC #: 14559 A | SDG #: BM\05 | 20506

### VALIDATION FINDINGS WORKSHEET Surrogate Results Verification

Page:_	
Reviewer:_	A
2nd reviewer:_	i
	7

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The p	ercent recoveries	(%R)	of surrog	gates were	e recalculated t	or the com	pounds identif	ied below ι	ising the f	following	calculation:
-------	-------------------	------	-----------	------------	------------------	------------	----------------	-------------	-------------	-----------	--------------

% Recovery: SF/SS \* 100

Where: SF = Surrogate Found

SS = Surrogate Spiked

Sample ID: 4

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8	400	379.27	95	95	0
Bromofluorobenzene		392.46	98	98	l
1,2-Dichloroethane-d4		387.79	91	97	
Dibromofluoromethane					·

Sam	ple	ID:

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8	٠.				i i
Bromofluorobenzene					
1,2-Dichloroethane-d4					
Dibromofluoromethane				-	14

Sample ID:\_

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8					
Bromofluorobenzene					
1,2-Dichloroethane-d4					,
Dibromofluoromethane					

Sample ID:

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8					
Bromofluorobenzene			·.		
1,2-Dichloroethane-d4					٠.
Dibromofluoromethane					

Sample ID:\_\_

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8			`		
Bromofluorobenzene					
1,2-Dichloroethane-d4					
Dibromofluoromethane	·				

LDC #:	145	99A	<u> </u>
SDG #:	BM	1051	20506

#### **VALIDATION FINDINGS WORKSHEET Laboratory Control Sample Results Verification**

Page:	_/of/
Reviewer:_	<i>F</i> 5
2nd Reviewer:_	

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The percent recoveries (%R) and Relative Percent Difference (RPD) of the laboratory control sample and laboratory control sample duplicate (if applicable) were recalculated for the compounds identified below using the following calculation:

% Recovery = 100 \* SSC/SA

Where: SSC = Spiked sample concentration

SA = Spike added

RPD = I LCS - LCSD I \* 2/(LCS + LCSD)

LCS = Laboractry control sample percent recovery

LCSD = Laboratory control sample duplicate percent recovery

LCS ID: \_\_\_\_ LCS - MSO73657A

	Sp	olke	Spiked S	ample	LC	s 1	LCS	n ]	LCS/I	CED
Compound	Ad	ded /kg/	Concent	ration	Percent R		Percent R		RF	
	LCS	LCSD	LCS	LCSD	Reported	Recalc.	Reported	Recalc.	Reported	Recalculated
1,1-Dichloroethene					·					
Trichloroethene										
Benzene ng lkg	400	NA	407	NA	102	102				
Toluene	400	V	403	1	101	101	N#			
Chlorobenzene TPH mg/kg	16	1	19	V	119	119				
OHIOTODETIZENO TPH my ky  Purquable										
3			·							
	·									
							÷			

Comments: Refer to Laboratory Control Sample findings worksheet for li	st of qualifications and associated samples	when reported results do not garee within 1	0.0%
of the recalculated results.	:		210/1

LDC#:_	14559A1	
	BM   05 120506	,

#### **VALIDATION FINDINGS WORKSHEET Sample Calculation Verification**

Page:_	<u>of</u>
Reviewer:	7
2nd reviewer:	1/
	A/

ME	: Tł	100th
Y	N	N/A
Y	N	N/A
		$\bigcup$

GC/MS VOA (EPA SW 846 Method 8260B)


Were all reported results recalculated and verified for all level IV samples? Were all recalculated results for detected target compounds agree within 10.0% of the reported results?

		•	
Concer	ntration	$A = \frac{(A_{\bullet})(I_{\bullet})(DF)}{(A_{\bullet})(RRF)(V_{\bullet})(\%S)}$	Example:
$\mathbf{A}_{\mathbf{x}_{-1}}$	·=	Area of the characteristic ion (EICP) for the compound to be measured	Sample i.D
A <sub>k</sub>	= '	Area of the characteristic ion (EICP) for the specific internal standard	
l <sub>s</sub> . , '	=	Amount of internal standard added in nanograms (ng)	Conc. = ( ) ( ) ( ) ( )
RRF	=	Relative response factor of the calibration standard.	
V <sub>o</sub>	=	Volume or weight of sample pruged in milliliters (ml) or grams (g).	= aw ND
Df	=	Dilution factor.	
<b>%</b> S	=	Percent solids, applicable to soils and solid matrices	

#	Sample ID	Compound		Reported Concentration ( )	Calculated Concentration	Qualification
	·		,		·	
	·					
		-				
		The state of the s				
	<u></u>		_			
$\rightarrow$			_			

### MCB Camp Pendleton, CTO 115 Data Validation Reports LDC# 14559

TPH as Purgeables



# Laboratory Data Consultants, Inc. Data Validation Report

Project/Site Name:

Camp Pendleton, CTO 115

Collection Date:

December 2, 2005

LDC Report Date:

January 27, 2006

Matrix:

Soil

Parameters:

Total Petroleum Hydrocarbons as Purgeables

Validation Level:

EPA Level III & IV

Laboratory:

Alpha Analytical, Inc.

Sample Delivery Group (SDG): BMI05120506

Sample Identification

43286-SV2

43286-SV1

43286-SV3

43286-SV4\*\*

<sup>\*\*</sup>Indicates sample underwent EPA Level IV review

#### Introduction

This data review covers 4 water samples listed on the cover sheet including dilutions and reanalysis as applicable. The analyses were per EPA SW 846 Method 8260B for Total Petroleum Hydrocarbons (TPH) as Purgeables.

This review follows a modified outline of the USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review (October 1999) as there are no current guidelines for the method stated above.

A qualification summary table is provided at the end of this report if data has been qualified. Flags are classified a P (protocol) or A (advisory) to indicate whether the flag is due to a laboratory deviation from a specified protocol or is of technical advisory nature.

Blank results are summarized in Section III.

Field duplicates are summarized in Section IX.

Samples indicated by a double asterisk on the front cover underwent a EPA Level IV review. A EPA Level III review was performed on all of the other samples. Raw data were not evaluated for the samples reviewed by Level III criteria since this review is based on QC data.

The following are definitions of the data qualifiers:

- U Indicates the compound or analyte was analyzed for but not detected at or above the stated limit.
- J Indicates an estimated value.
- R Quality control indicates the data is not usable.
- N Presumptive evidence of presence of the constituent.
- UJ Indicates the compound or analyte was analyzed for but not detected. The sample detection limit is an estimated value.
- A Indicates the finding is based upon technical validation criteria.
- P Indicates the finding is related to a protocol/contractual deviation.
- None Indicates the data was not significantly impacted by the finding, therefore qualification was not required.

#### I. Technical Holding Times

All technical holding time requirements were met.

The chain-of-custodies were reviewed for documentation of cooler temperatures. All cooler temperatures met validation criteria.

#### II. GC/MS Instrument Performance Check

Instrument performance was checked at 12 hour intervals.

All ion abundance requirements were met.

#### III. Initial Calibration

Initial calibration was performed using required standard concentrations.

Percent relative standard deviations (%RSD) were less than or equal to 30.0% for all compounds.

#### IV. Continuing Calibration

Continuing calibration was performed at the required frequencies.

Percent differences (%D) between the initial calibration RRF and the continuing calibration RRF were within the method criteria of less than or equal to 25.0% for all compounds.

#### V. Blanks

Method blanks were reviewed for each matrix as applicable. No total petroleum hydrocarbons as purgeable contaminants were found in the method blanks.

#### VI. Surrogate Spikes

Surrogates were added to all samples and blanks as required by the method. All surrogate recoveries (%R) were within QC limits.

#### VII. Matrix Spike/Matrix Spike Duplicates

The laboratory has indicated that there were no matrix spike (MS) and matrix spike duplicate (MSD) analyses specified for the samples in this SDG, and therefore matrix spike and matrix spike duplicate analyses were not performed for this SDG.

#### VIII. Laboratory Control Samples (LCS)

Laboratory control samples were reviewed for each matrix as applicable. Percent recoveries (%R) and relative percent differences (RPD) were within QC limits.

#### IX. Regional Quality Assurance and Quality Control

Not applicable.

#### X. Internal Standards

All internal standard areas and retention times were within QC limits.

#### XI. Target Compound Identifications

All target compound identifications were within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

#### XII. Compound Quantitation and CRQLs

All compound quantitation and CRQLs were within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

#### XIII. Tentatively Identified Compounds (TICs)

Tentatively identified compounds were not reported by the laboratory.

#### XIV. System Performance

The system performance was within validation criteria for samples on which a EPA Level IV review was performed. Raw data were not evaluated for the samples reviewed by Level III criteria.

#### XV. Overall Assessment of Data

Data flags are summarized at the end of this report if data has been qualified.

#### XVI. Field Duplicates

No field duplicates were identified in this SDG.

#### XVII. Field Blanks

No field blanks were identified in this SDG.

Camp Pendleton, CTO 115
Total Petroleum Hydrocarbons as Purgeables - Data Qualification Summary - SDG
BMI05120506

No Sample Data Qualified in this SDG

Camp Pendleton, CTO 115
Total Petroleum Hydrocarbons as Purgeables - Laboratory Blank Data Qualification
Summary - SDG BMI05120506

No Sample Data Qualified in this SDG



## Alpha Analytical, Inc.

255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

#### **ANALYTICAL REPORT**

Battelle Memorial Institute 505 King Avenue Columbus, OH 43201 Attn: Bob Janosy Phone: (614) 424-7160 Fax: (614) 424-3667 Date Received: 12/03/05

Job#:

TO115/43286

Total Petroleum Hydrocarbons - Purgeable (TPH-P) EPA Method SW8015B/DHS LUFT Manual Volatile Organic Compounds (VOCs) EPA Method SW8260B

	Parameter	Conce	entration	Reporting	Date	Date
				Limit	Sampled	Analyzed
Client ID:	TPH Purgeable	ND	U	1.0 mg/Kg	12/02/05	12/09/05
43286-SV2	Methyl tert-butyl ether (MTBE)	ND		5.0 μg/Kg	12/02/05	12/09/05
Lab ID:	Benzene	ND		5.0 µg/Kg	12/02/05	12/09/05
BMI05120506-01A	Toluene	ND		5.0 μg/Kg	12/02/05	12/09/05
	Ethylbenzene	ND		5.0 μg/Kg	12/02/05	12/09/05
	m,p-Xylene	ND		5.0 µg/Kg	12/02/05	12/09/05
	o-Xylene	ND		5.0 µg/Kg	12/02/05	12/09/05
	Surr: 1,2-Dichloroethane-d4	98		%REC	12/02/05	12/09/05
	Surr: Toluene-d8	97		%REC	12/02/05	12/09/05
	Surr: 4-Bromofluorobenzene	94		%REC	12/02/05	12/09/05
Client ID:	TPH Purgeable	7.0	•	1.0 mg/Kg	12/02/05	12/07/05
43286-SV1	Methyl tert-butyl ether (MTBE)	ND	<i></i>	5.0 μg/Kg	12/02/05	12/07/05
Lab ID:	Benzene	ND		5.0 μg/Kg	12/02/05	12/07/05
BM105120506-02A	Toluene	ND		5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	18		5.0 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	15		5.0 μg/Kg	12/02/05	12/07/05
	e-Xylene	ND		5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	97		%REC	12/02/05	12/07/05
	Surr: Toluene-d8	95		%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98		%REC	12/02/05	12/07/05
Client ID:	TPH Purgeable	ND	u	1.0 mg/Kg	12/02/05	12/07/05
43286-SV3	Methyl tert-butyl ether (MTBE)	ND		5.0 μg/Kg	12/02/05	12/07/05
Lab ID:	Benzene	ND		5.0 μg/Kg	12/02/05	12/07/05
BMI05120506-03A	Toluene	ND		5.0 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	ND		5.0 µg/Kg	12/02/05	12/07/05
	m,p-Xylene	ND		5.0 μg/Kg	12/02/05	12/07/05
	o-Xylene	ND		5.0 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	98		%REC	12/02/05	12/07/05
	Surr: Toluene-d8	97		%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98		%REC	12/02/05	12/07/05



## Alpha Analytical, Inc.

255 Glendale Ave. • Suite 21 • Sparks, Nevada 89431-5778 (775) 355-1044 • (775) 355-0406 FAX • 1-800-283-1183

Client ID:	TPH Purgeable	39		2.0 mg/Kg	12/02/05	12/07/05
Chem ID :	ŭ			2.0 mg/Kg		
43286-SV4	-Methyl tert-butyl ether (MTBE)	ND	V	10 μg/Kg	12/02/05	12/07/05
Lab ID:	Benzene	ND	V	10 μg/Kg	12/02/05	12/07/05
BMI05120506-04A	Toluene	ND	V	10 μg/Kg	12/02/05	12/07/05
	Ethylbenzene	ND	V .	10 μg/Kg	12/02/05	12/07/05
	m,p-Xylene	ND	V	10 μ <b>g/K</b> g	12/02/05	12/07/05
	Xylene	ND	- <del>V</del>	10 μg/Kg	12/02/05	12/07/05
	Surr: 1,2-Dichloroethane-d4	97		%REC	12/02/05	12/07/05
	Surr: Toluene-d8	95		%REC	12/02/05	12/07/05
	Surr: 4-Bromofluorobenzene	98		%REC	12/02/05	12/07/05

V = Reporting Limits were increased due to high concentrations of target analytes.

ND = Not Detected

Roger L. Scholl, Ph.D., Laboratory Director · Randy Gardner, Laboratory Manager · Walter Hinchman, Quality Assurance Office Sacramento, CA · (916) 366-9089 / Las Vegas, NV · (702) 281-4848 / info@alpha-analytical.com

12/13/05

Report Date

LDC #: 14559A7	VALIDATION COMPLETENESS WORKSHEET	Date: 1/2 6/00
SDG #: BMI05120506	Level III/IV	Page: <u>/</u> of <u>/</u> ′
Laboratory: Alpha Analytical, Inc	)	Reviewer:
METHOD: GC/MS TPH as Purg	reables (EPA SW 846 Method 8260B)	2nd Reviewer:
The samples listed below were	reviewed for each of the following validation areas. Validation fin	dings are noted in attached

validation findings worksheets.

	Validation Area		Comments
l.	Technical holding times	Δ	Sampling dates: 12/2/05
II.	GC/MS Instrument performance check	Α	
III.	Initial calibration	A	% PSP = 30
IV.	Continuing calibration	Δ	%ロニズ
V.	Blanks	Λ	
VI.	Surrogate spikes	A	
VII.	Matrix spike/Matrix spike duplicates	2	Chint specifical
VIII.	Laboratory control samples	<b>*</b>	vc>
IX.	Regional Quality Assurance and Quality Control	N	
Χ.	Internal standards	Δ	
XI.	Target compound identification	Δ	Not reviewed for Level III validation.
XII.	Compound quantitation/CRQLs	A	Not reviewed for Level III validation.
XIII.	Tentitatively identified compounds (TICs)	2	Not reviewed for Level III validation. not reported
XIV.	System performance	A	Not reviewed for Level III validation.
XV.	Overall assessment of data	Δ	
XVI.	Field duplicates	N	
XVII.	Field blanks	N	


Note:

A = Acceptable N = Not provided/applicable SW = See worksheet

ND = No compounds detected D = Duplicate
R = Rinsate TB = Trip blank
FB = Field blank EB = Equipment blank

Validated Samples: \*\* Indicates sample underwent Level IV validation

	SOIL						
1	43286-SV2	11	MBLK MS0753	269	57B	31	
2	43286-SV1	12		22		32	
3	43286-SV3	13		23		33	
4	43286-SV4**	14		24		34	
5		15		25		35	
6		16		26		36	
7		17		27		37	
8		18		28		38	
9		19		29		39	
10		20		30		40	




#### VALIDATION FINDINGS CHECKLIST

Page: \_\_\_\_of\_\_\_\_ Reviewer: \_\_\_\_\_\_\_ 2nd Reviewer: \_\_\_\_\_\_

Method: Volatiles (EPA SW 846 Method 8260B)

Method: Volatiles (EPA SW 846 Method 8260B)				
Validation Area	Yes	No	NA	Findings/Comments
It. Technical holding times.		Economic Services		
All technical holding times were met.  Cooler temperature criteria was met.	/			
II. GC/MS Instrument performance check				
Were the BFB performance results reviewed and found to be within the specified criteria?	/			
Were all samples analyzed within the 12 hour clock criteria?	/			
III. Initial calibration				A Committee of the Comm
Did the laboratory perform a 5 point calibration prior to sample analysis?	V			
Were all percent relative standard deviations (%RSD) and relative response factors (RRF) within method criteria for all CCCs and SPCCs?	/			
Was a curve fit used for evaluation?		_	_	
Did the initial calibration meet the curve fit acceptance criteria of > 0.990?				
Were all percent relative standard deviations (%RSD) ≤ 30% and relative response factors (RRF) ≥ 0.05?				
IV. Continuing calibration				
Was a continuing calibration standard analyzed at least once every 12 hours for each instrument?	/			
Were all percent differences (%D) and relative response factors (RRF) within method criteria for all CCCs and SPCCs?	/			
Were all percent differences (%D) ≤ 25% and relative response factors (RRF) ≥ 0.05?	/			
V. Blanks				
Was a method blank associated with every sample in this SDG?	/			
Was a method blank analyzed at least once every 12 hours for each matrix and concentration?	/			
Was there contamination in the method blanks? If yes, please see the Blanks validation completeness worksheet.		V		
VI. Surrogate spikes				no con them is
Were all surrogate %R within QC limits?	/			
If the percent recovery (%R) for one or more surrogates was out of QC limits, was a reanalysis performed to confirm samples with %R outside of criteria?			_	
VII. Matrix spike/Matrix spike duplicates				
Were a matrix spike (MS) and matrix spike duplicate (MSD) analyzed for each matrix in this SDG? If no, indicate which matrix does not have an associated MS/MSD. Soil / Water.			_	
Was a MS/MSD analyzed every 20 samples of each matrix?			-	
Were the MS/MSD percent recoveries (%R) and the relative percent differences (RPD) within the QC limits?				
VIII. Laboratory control samples		( ) a	a tile	· State of the second s
Was an LCS analyzed for this SDG?	-			



#### VALIDATION FINDINGS CHECKLIST

Validation Area	Yes	No	NA	Findings/Comments
Was an LCS analyzed per analytical batch?				
Were the LCS percent recoveries (%R) and relative percent difference (RPD) within the QC limits?			5012-05-001-001	
IX. Regional Quality Assurance and Quality Control			1	
Were performance evaluation (PE) samples performed?			/	
Were the performance evaluation (PE) samples within the acceptance limits?	is with	1900		-
Were internal standard area counts within -50% or +100% of the associated callbration standard?				
Were retention times within + 30 seconds of the associated calibration standard?				
XI. Target compound identification				Company of the Compan
Were relative retention times (RRT's) within ± 0.06 RRT units of the standard?	/			
Did compound spectra meet specified EPA "Functional Guidelines" criteria?	/			
Were chromatogram peaks verified and accounted for?			No.	
XII. Compound quantitation/CRQLs				Secretary of the second of the
Were the correct internal standard (IS), quantitation ion and relative response factor (RRF) used to quantitate the compound?				
Were compound quantitation and CRQLs adjusted to reflect all sample dilutions and dry weight factors applicable to level IV validation?	/			
XIII, Tentatively identified compounds (TICs)				p space.
Were the major ions (> 10 percent relative intensity) in the reference spectrum evaluated in sample spectrum?				-
Were relative intensities of the major ions within ± 20% between the sample and the reference spectra?			_	
Did the raw data indicate that the laboratory performed a library search for all required peaks in the chromatograms (samples and blanks)?			_	
XIV. System performance				
System performance was found to be acceptable.	_			
XV. Overall assessment of data				
Overall assessment of data was found to be acceptable.		-		
XVI. Field duplicates				100
Field duplicate pairs were identified in this SDG.		/	-	
Target compounds were detected in the field duplicates.			/	
XVII. Field blanks				
Field blanks were identified in this SDG.		/	-	
Target compounds were detected in the field blanks.			_	

LDC #: 14559A7 SDG #: BMI 05120506

### VALIDATION FINDINGS WORKSHEET Initial Calibration Calculation Verification

	Page:_	of	1
	Reviewer:	<b>7</b>	
2nd	Reviewer:	Ŕ	
	-		

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The Relative Response Factor (RRF), average RRF, and percent relative standard deviation (%RSD) were recalculated for the compounds identified below using the following calculations:

RRF =  $(A_y)(C_h)/(A_h)(C_y)$ average RRF = sum of the RRFs/number of standards %RSD = 100 \* (S/X)

 $A_x$  = Area of compound,

A<sub>k</sub> = Area of associated internal standard

 $C_{x} =$ Concentration of compound,

C<sub>k</sub> = Concentration of Internal standard

S = Standard deviation of the RRFs

X = Mean of the RRFs

				Reported	Recalculated	Reported	Recalculated	Reported	Recalculated
#	Standard ID	Calibration Date	Compound (Reference Internal Standard)	RRF ( 식이ට std)	RRF ( 40 Gtd)	Average RRF (initial)	Average RRF (initial)	%RSD	%RSD
1	MS07 ICAL	12/2/05	Methylena chlorde (1st internal standard)	2.033	2.033	1907	1.907	0/ 7	8-7
	1412		Trichiorethene (2nd internal standard)					8.7	8-/
			Toluene (3rd internal standard)						
2			Methylene chloride (1st internal standard)						
			Trichlorethene (2nd Internal standard)						<del> </del>
			Toluene (3rd internal standard)						
3			Methylene chloride (1st internal standard)						
			Trichlorethene (2nd internal standard)						
			Toluene (3rd internal standard)						
4			Methylene chloride (1st internal standard)						
			Trichlorethene (2nd internal standard)						
			Toluene (3rd Internal standard)						<del> </del>

Comments: Refer to Initial Calibration findings worksheet for list of qualifications and associated samples when reported results do not agree within 10.0% of the recalculated results.

LDC i	#:1	45	559	A	7
SDG	#:	13	MI	05	120506

#### **VALIDATION FINDINGS WORKSHEET Continuing Calibration Results Verification**

	Page:_	of	
1	Reviewer:	1	
2nd l	Reviewer:		

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The percent difference (%D) of the initial calibration average Relative Response Factors (RRFs) and the continuing calibration RRFs were recalculated for the compounds identified below using the following calculation:

% Difference = 100 \* (ave. RRF - RRF)/ave. RRF  $RRF = (A_{\star})(C_{\mathtt{h}})/(A_{\mathtt{h}})(C_{\star})$ 

Where: ave. RRF = Initial calibration average RRF

RRF = continuing calibration RRF

 $A_x =$ Area of compound,

A<sub>k</sub> = Area of associated internal standard

C<sub>x</sub> = Concentration of compound, C<sub>h</sub> = Concentration of internal standard

					Reported	Recalculated	Reported	Recalculated
#	Standard ID	Calibration Date	Compound (Reference Internal Standard)	Average RRF (initial)	RRF (CC)	RRF (CC)	%D	%D
1	05120707	12/7/05	Methylandohloridi (1st internal standard)	1.907	2-31	2-311	21.2	21.2
		• 1	Trichlerethene (2nd internal etandard)	·				
<u></u>			Tolumno (3rd-internal standard)					·
2			Methylene chloride (1st internal standard)					
			Trichlorethene (2nd internal standard)					
<u></u>			Toluene (3rd internal standard)					
3			Methylene chloride (1st internal standard)					
	· '		Trichlorethene (2nd internal standard)					
		· · · · · · · · · · · · · · · · · · ·	Toluene (3rd internal standard)					
4			Methylene chloride (1st internal standard)					
			Trichlorethene (2nd internal standard)		V A			
<u></u>			Toluene (3rd internal standard)					

Comments:	Refer to	Continuing	Calibration	findings	worksheet for	list of qua	lifications	and	associated	samples	when rep	orted res	sults do r	not agra	e within	10.0% of the
recalculated	results.											<u> </u>	Julio GO I	iot agre	O WIGHT	10.078 01 1116
											,					
								<del></del>								

LDC #: 14559 A7 SDG #: BM 105 120506

## VALIDATION FINDINGS WORKSHEET <u>Surrogate Results Verification</u>

Page:	
Reviewer:	
2nd reviewer:	
	7

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The p	ercent recoveries	(%R)	of surrogates wer	e recalculated t	or the compounds	identified below	w using the	∍ following a	calculation:
-------	-------------------	------	-------------------	------------------	------------------	------------------	-------------	---------------	--------------

% Recovery: SF/SS \* 100

Where: SF = Surrogate Found

SS = Surrogate Spiked

Sample ID: 4

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference	
Toluene-d8	400	379.27	95	95	0	
Bromofluorobenzene		392.66	98	98		
1,2-Dichloroethane-d4		367.79	91	97	· V	
Dibromofluoromethane				L		

Sample ID:\_

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8					
Bromofluorobenzene			4		
1,2-Dichloroethane-d4		·			
Dibromofluoromethane					

Sample ID:

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8		·			
Bromofluorobenzene					
1,2-Dichloroethane-d4				-	,
Dibromofluoromethane					

Sample ID:\_\_\_

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8					
Bromofluorobenzene			1.		
1,2-Dichloroethane-d4					
Dibromofluoromethane					

Sample ID:\_

	Surrogate Spiked	Surrogate Found	Percent Recovery Reported	Percent Recovery Recalculated	Percent Difference
Toluene-d8					
Bromofluorobenzene					
1,2-Dichloroethane-d4					
Dibromofluoromethane			·		

LDC #	146	591	47
			20506

## **VALIDATION FINDINGS WORKSHEET Laboratory Control Sample Results Verification**

Page:	
Reviewer:_	19
2nd Reviewer:_	e

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

The percent recoveries (%R) and Relative Percent Difference (RPD) of the laboratory control sample and laboratory control sample duplicate (if applicable) were recalculated for the compounds identified below using the following calculation:

% Recovery = 100 \* SSC/SA

Where: SSC = Spiked sample concentration

SA = Spike added

RPD = ILCS - LCSD I \* 2/(LCS + LCSD)

LCS = Laboractry control sample percent recovery

LCSD = Laboratory control sample duplicate percent recovery

LCS ID: GLCS MS0753657B

Compound	Spike Spiked Sample Added Concentration		Sample ntration	LCS		LCSD		LCS/LCSD		
Compound	(m	glax	(my tr		Percent Recovery		Percent Recovery		RPD	
	LCS	LCSD	LCS	LCSD	Reported	Recaic.	Reported	Recalc.		T
1,1-Dichloroethene					·			Necalc.	Reported	Recalculated
Trichloroethene				<b>-</b>						
Benzene				<del> </del>	<del> </del>					
Toluene					<del> </del>					
Chlorobenzene										
TPH purgeable	16	NA	19	NA	119	119	NA			
	·									
										<del> </del>
			·						· · · · · · · · · · · · · · · · · · ·	<u> </u>
				<del></del>						
		<del> </del>		· · · · · · · · · · · · · · · · · · ·	<b></b>					

Comments: Refer to Laboratory Control Sample findings workshoot for the same time	
Comments: Refer to Laboratory Control Sample findings worksheet for list of qualification of the recalculated results.	ations and associated samples when reported results do not agree within 10.0%
	1131 agree Within 10,078

LDC #: 14559A7 SDG #: BM | 05 | 20506

## VALIDATION FINDINGS WORKSHEET Sample Calculation Verification

Page: \_\_/ of \_/ Reviewer: \_\_/5 2nd reviewer: \_\_\_\_

METHOD: GC/MS VOA (EPA SW 846 Method 8260B)

Y N/A Were all reported results recalculated and verified for all level IV samples?

Y N N/A Were all recalculated results for detected target compounds agree within 10.0% of the reported results?

Concentration = (A,)(I,)(DF)
(A<sub>k</sub>)(RRF)(V<sub>0</sub>)(%S)

A<sub>x</sub> = Area of the characteristic ion (EICP) for the compound to be measured

A<sub>k</sub> = Area of the characteristic ion (EICP) for the specific internal standard

I<sub>x</sub> = Amount of internal standard added in nanograms (ng)

RRF = Relative response factor of the calibration standard.

V<sub>o</sub> = Volume or weight of sample pruged in milliliters (ml) or grams (g).

Df = Dilution factor.

%S = Percent solids, applicable to soils and solid matrices only.

Example:

Sample I.D. #4, TPH: purgeable

Conc. = (154631630 (19) (40), (808257) (1.907) 1000

40 mg/kg

<u> </u>	only.	T	i i		
			Reported Concentration	Calculated Concentration	}. ·
#	Sample ID	Compound	( )	( )	Qualification
			·		
	:			·	
		·			
-			·		
	·				
	·				
	·				
		·			

